

Gunjan and Associates
Architects, Engineers, Interiors
& Landscape Designers

141,Sainik Nagar,Raibareli Road, Lucknow-226002

Phone: 0522-2441118, 9839018489, 9838818489

E-mail:sudio@gunjanandassociates.com

URL:www.gunjanandassociates.com

BOQ FOR AIR-CONDITIONING WORKS

FOR INDIAN BANK, AT KAISERGANJ, BRANCH & A.T.M

Note;

1. Each vendor to specify the Make of A.C. they propose to supply.
2. Common drain pipes of Cassette / Split A.C.'s be terminated in any toilet Nahni traps OR else be terminated from external wall up to ground. AC's with COPPER Condenser & Evaporator coils only to be supplied.
3. Pl. enclose Technical Brocher of quoted A.C.'s.
4. As built layout drawing of Refrigerant & Drain Piping has to be attached with Final Bill.

Daikin, Hitachi, . AC's with COPPER Condenser & Evaporator coils should only be supplied.

Only one of these Makes to be quoted.

Pl. enclose Tech. Brocher of the quoted Cassette/ Split A.C.

S.N.	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
1	High Wall Split Inverter AC 1.0 Ton 5 star rating	No	4.00		
	SITC Of wall mounted split Inverter type AC 1.0 Ton 5 star.(AC MAKE of -VOLTAS DAIKIN,HITACHI `ONLY APPROVAL AS PER ARCHITECT with 5 year warranty on compressor and ecofriendly green gas.				
2	High Wall Split Inverter AC 1.5 Ton 5 star rating	No	4.00		
	SITC Of wall mounted split Inverter type AC 1.5 Ton 5 star.(AC MAKE of -VOLTAS DAIKIN,HITACHI `ONLY APPROVAL AS PER ARCHITECT with 5 year warranty on compressor and ecofriendly green gas.				
3	Rate for Extra Piping (Rate above 12 Feet pipe which will be free with unit)Ref.Piping(Only single distance will be measured between Indoor & Outdoor Units)				

a	Copper Piping Refrigerant along with insulator Piping for Hi Wall 1.5 ton ,1 ton and 2 ton Ac 1/2 and 1/4 Soft Copper Refrigerant piping with complete fitting, elbows bends supporting arrangements Nissan, Merchant, MET tube, Totaline tube, pressure tested tube .	Rm	50.00		
4	S.I.T.C. of 4 core Copper conductor flexible cable between Indoor &	Rm	60.00		
	Outdoor Unit through holes made as above				
5	Frame Work Supply, Fabrication and installation Of MS base Frame for outdoor unit complete with epoxy painting vibration isolation pads, supports, hangers, railing brackets etc. with cage and lockning arrangement.	No	8.00		
6	Drain Water Piping Constructed out of PVC Hard Pipes, fitting, accessories, bends, elbows, tees, hanger, support, anchors, ISI approved Finolex/Prince Make (32mm)	RMT	50.00		
7	Providing & Installation of 4KVA voltage Stabilizers with range of 130 - 280V of standard make as per the approval of the Architect of (Inmag, Servel,Stambh)	No	6.00		
8	Repair and maintainance of existing stablizers	No	2.00		
9	Comissioning and gas recharging of the existing Acs	No	2.00		
	Total				

For GUNJAN & ASSOCIATES

 (Ar. GUNJAN KAPUR)
 PROPRIETOR

Ar. Gunjan Kapur

M/s Gunjan & Associates