



Schedule of Quantities for laying of cement concrete interlocking paver block in the Bank's premises at Meerut Cantt.

S no	DESCRIPTION OF ITEM	UNIT	QUANTITY	RATE	AMOUNT
1	Providing and laying 80mm thick factory made cement concrete interlocking paver block of M -35 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge.	Sqm	260		
2	Brick edging laid lengthwise with half brick depth including excavation, refilling and disposal of surplus earth lead upto 50 metres : With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	RM	50		
3	Providing and laying cement concrete 1:2:4 (1cement: 2coarse sand: 4graded stone aggregate 20mm or below for filling the external border.	Cum	2		
4	Taking out cattle catcher and re fixing the same in cement concrete after clearing the drain and making proper slope to drain out the rain water under the cattle catcher.	LS	1		
			TOTAL		
Add contingencies 10%					
			GRAND TOTAL		

Place :

Contractor's sign with stamp

Date: