

INDIAN BANK,

ZONAL OFFICE,

Delhi Central,

Ph: 011-23745506/23745504

PART - 2: PRICE BID

Tender document for "Design, Engineering, Supply, Installation, Testing and Commissioning of 15 kWp at G-41, Connaught Place, Delhi-110001) Grid interactive Solar Photo Voltaic system" at Indian Bank, own premises".

ISSUED TO

M/s. _____

(This document contains 06 pages)



Sr No	Description	Qty	Unit	Supply			Installation		Total Amount S+I (excluding tax)
				Rate	Amount	Supply	Amount	Amount	

LOCATION : G-41, Connaught Place, Delhi-110001 -15 kWp									
1	DESITC of 540 Wp Monocrystalline solar PV panels as per technical specifications given in the Tender (If higher wattage capacity panels are used, the power output of 15 kWp to be maintained).	28	No						
2	DESITC of 15 KW (or higher) solar inverter as per technical specifications and safety mat for operating personnel etc.	1	No						
3	DESITC of Weather proof IP-65 array junction box with SPD, Fuse and as per technical specifications etc. (minimum 02 nos)	2	No						
4	DESITC of IP-42 protected cubicle type panel (ACDB) wall mounting fitted with all accessories (with AC surge arrester, fuse etc) and suitable rating 32 A, 25 KA 4 Pole MCCB (Current rating to be adjustable in the range from 80 % - 100%) to evacuate power (near to the inverter); with all necessary accessories and supply & installation of 1 no. 32 A, 25 KA 4P, MCCB (Current rating to be adjustable in the range from 80 % - 100%) (near to the mains of the Branch) with suitable enclosure to terminate the solar power supply to the mains of the Branch, as per technical specifications and safety mat shall be provided for operating personnel etc.	1	set						

Sr No	Description	Qty	Unit	Supply		Installation		Total Amount S+I (excluding tax)
				Rate	Amount	Supply	Amount	
5	Earthing of solar panel structures and AC DB Supply and fixing GI pipe earth station conforming fully to IS 3043 with latest amendments, complete with 3 m long 17.2mm dia GI cooper coated, 150 micron with Funnel on Top with holes drilled for tapping connection. The rate includes making 300 mm diameter pit and after excavation pit to be filled with to surface with alternate layer of salt/charcoal mixture. Brick work masonry shall be constructed of size 450x450x300 mm with RCC cover. Note: Test report of resistance of the new earth pit to be submitted. (2 nos for DC, 2 nos for AC and 2nos for Lighting arrestor).	3	No					
5.2	DESITC of 25 x 3 MM GI Strip to be clamped on wall, cable tray, buried in ground to interconnect the earth electrodes mentioned above (5.1) to the solar panel structures and power evacuation panel / combiner panel , lighting arrestor separately (The GI strip shall be painted with green paint as per electrical inspectorate norms).	100	Mt					
5.3	DESITC of 4 core 10 Sq mm Dia multi-stranded Cu wire, FRPVC insulated green colored cable to be drawn in 20 MM Dia PVC conduit, 1.5MM thick to be clamped on wall, cable tray, buried in ground to interconnect the earth electrode with	100	Mt					

Sr No	Description	Qty	Unit	Supply		Installation		Total Amount S+I (excluding tax)
				Rate	Amount	Supply	Amount	
	inverter neutral point, AC DB to Inverter including terminations at both the ends etc.							
6	DESITC of AC & DC cabling between panels and inverter with heat resistant insulated copper wires drawn in UPVC Conduit properly fixed properly on pedestals on the floor for interconnection between solar modules, ARJ and inverter.	1	Lot					
7	DESITC of 4C x 16 Sqmm aluminum armored cable from AC Distribution Board to spare feeder of Main LT panel situated at the ground floor including terminations at both ends. The gland earthing with 14 SWG copper wire and connecting the same to earth grid to be included in the rate quoted by the contractor.	100	Mt					
8	Design, fabrication, supply and installation of concrete pedestals of minimum M20 grade [(1:1 1/2:3)] and the same shall be plastered with 12mm thick cement sand mortar of ratio 1:4 of 300mm wide x 450mm high to be fixed on terrace floor for supporting solar panel structures. And the pedestals shall be painted with exterior emulsion paint.	1	Lot					
9	Design & Supply, Installation of GI structures for supporting the solar panels as per technical specifications	1	Lot					
10	Supply & Installation of safety items like fire extinguishers, fire buckets and danger boards / Signages / Identification stickers on modules / inverters / Array junction box etc., / first aid kit	1	Lot					



Sr No	Description	Qty	Unit	Supply		Installation		Total Amount S+I (excluding tax)
				Rate	Amount	Supply	Amount	
	etc., and safety mat at the location of inverters / combiner panel etc., Shock treatment chart both in Hindi & English, as required and which found necessary as per electrical inspectorate norms.							
11	Supply and installation of 3 prong copper spike lightning terminal on 3 Mt. high GI pipe with anchoring to be mounted on the parapet wall with proper clamping arrangement. Lightning protection terminals as required to protect the entire building including the solar installation with GI strip / copper down conductors and earth pit as per IS standard each for Lightning terminal / mast.	2	Nos					
12	Liaison with respective State Electricity, Board and Electrical Inspectorate for zero export	1	Job					
13	Liaisoning with Govt agencies for project approval) and Preparation of as-built drawings, SLD etc., Liaisoning with CEA / Government agencies (respective State Electricity Board / MNRE/other govt agencies) after arranging inspection and getting approval and arrange for , subsidy etc. after completion.	1	Job					
14	Auto sprinkler system for automatic cleaning for solar panels	1	Job					
	Sub Total							
	Grand total for Supply and Installation – (A)							



Sr No	Description	Qty	Unit	Supply		Installation		Total Amount S+I (excluding tax)
				Rate	Amount	Supply	Amount	
14	Operation & Maintenance (O&M) of Solar PV System (To be considered for Tender evaluation purpose)							
14.a	O&M During DL period	01	Year					
14.b	O&M for the 1st year after DLP	01	Year					
14.c	O&M for the 2nd year after DLP	01	Year					
14.d	O&M for the 3rd year after DLP	01	Year					
14.e	O&M for the 4th year after DLP	01	Year					
14.f	O&M for the 5th year after DLP	01	Year					
	O&M - SUB TOTAL -----(B)							
	GRAND TOTAL (A+ B) – (Exclusive of all taxes)							

