

Zonal Office:Gonda

NOTICE INVITING TENDER

Sub: COMPETITIVE QUOTATION FOR INTERIOR FURNISHING AND ELECTRICAL AND DATA NETWORK CABLING WORK OF SADULLANAGAR BRANCH DISTT BALRAMPUR UNDER GONDA ZONE

Competitive sealed quotations are invited in the prescribed format from the contractors who are already empanelled with bank executed interior furnishing of nationalized Banks in last three years.

Formats of Quotations document is enclosed for submission of interior furnishing and Electrical and Data network Cabling work of **SADULLANAGAR** branch, Distt- Balrampur. Full details and tender document are available in Bank's website www.indianbank.in or can be obtained from Zonal Office Gonda. Duly filled tenders should be submitted as per following schedule:

JOHU	a. Duly filled terracio erro	
4	Issue of Tender Document	From 08.01.2024 to 20.01.2024
1	Issue of Terider Document	On or before 20.01.2024 up to 5:00PM
2	Subillission of Lendo.	On 22.01.2024 at 03.00 PM
3	Opening of Tender	Rs5.76 Lakh
4	Estimated cost of work	RS5.70 Lakii
		7 Days from the date of issue of letter awarding the job
5	Date of Commencement	
6	Time of Completion	20 days
7	Defect Liability Period	12 Months
	Earnest Money	Rs.5000/- in form of DD/IOI in favour of Indian Bank payable at Gonda.
8	Earnest Money	wistered with MSMF/NSIC WILL Valle Certificate location by
	9	
	The second of th	
9	Liquidated Damages for delay	
		and not as penalty during which the work remains un-commenced or
		and the completion date
		t and Interim haven will be illade, I dyllion
10	Payment Terms	Neither any advance nor any interim payment will be made on satisfactory completion of the job on the basis of actual will be made on satisfactory completion of the job on the basis of actual will be made on satisfactory complete by deducted as per the rules.
10		will be made on satisfactory completion of the just an experiments. Income tax will be deducted as per the rules.
		measurements. Income tax will be deducted as per the rules. Retention money 10% will be deducted the bill and to be released after
		Retention money 10% will be deducted the bill and to be defects
		12 months from the date of virtual completion provided no defects
		is observed during this period.
11	Document to be attached with	is observed during this period. Manager completion Certification Bills & 4-5 Manager completion Certification of work
11	the Bill	photographs showing completion status of work.
10		10% (Including Earnest money)
12	Retention Money	

The Bank will not be bound to accept the lowest tender and reserves the right to accept or reject any or all the tender without assigning any reason whatsoever. Late/delayed tender shall not be accepted after due date and time of submission of tender.

Zonal Manager





CLIENT INDIAN BANK

<u>seal</u>

ZONAL OFFICE GONDA- Premises Department Bahraich Road, Near Roadways Bus stop Gonda Uttar Pradesh-227001

WORK /PROJECT

PROPOSED INTERIOR FURNISHING AND ELECTRICAL AND DATA NETWORK CABLING WORK OF SADULLANAGAR BRANCH-DISTT BALRAMPUR UNDER GONDA ZONE

COMPETITIVE QUOTATION FOR INTERIOR FURNISHING AND ELECTRICAL AND DATA NETWORK CABLING WORK AT ABOVE PROJECT

Tender Issued to
M/S
Address
Contact No
Tender Issued on :
Last Date ofSubmission :
Signature of the Contractor





Zonal Office: GONDA

NOTICE INVITING TENDER

Sub: COMPETITIVE QUOTATION FOR INTERIOR FURNISHING AND ELECTRICAL AND DATA NETWORK CABLING WORK OF SADULLANAGAR BRANCH-DISTT BALRAMPUR UNDER GONDA ZONE

Sealed quotation should be addressed to The Zonal Manager, Indian Bank, Zonal Office Gonda and super scribed name of Work Interior Furnishing and Electrical and Data Network Cabling Work of SADULLANAGAR Branch, at SADULLANAGAR, Distt- BALRAMPUR and should reach before 5:00 p.m. on 20.01.2024 at Zonal Office Gonda.

Mailing Address:

The Zonal Manager, INDIAN BANK

Zonal Office Gonda

Bahraich Road,Near Roadways Bus Stop, Gonda-271001(U.P)

- 2) No quotation will be accepted after 5:00 pm on 20.01.2024 and quotations will be opened on 22.01.2024 at 3:00 pm unless otherwise informed.
- The quotations will remain valid for a period of 3 months from the date of opening.
- Bank reserves the right to accept or reject any or all the quotations accept part of any tender, entrust the entire work to any contractor or divide the work to more than one contractor (item wise) without assigning any reason to do so or giving any explanation. The rates quoted by the contractors will help well for bifurcation and no compensation will be paid on this account.
- At the time of submission every quotation must be accompanied by IOI/ Demand Draft for an amount of Rs.5000/- in favour of INDIAN BANK payable at Gonda towards EMD. Any quotation which is not accompanied by EMD will be summarily rejected. *Firms registered with MSME/NSIC with valid certificate issued by GOI are exempted from submitting EMD along with Tender.
- Contract should quote rates in figures as well as in words.
- All erasures and alterations made must be attested with the initials of tenderers. No overwriting is permitted.
- 8) The EMD of the unsuccessful bidders will be returned within 45 days from the date of opening the tender.
- Joint tenders shall not be considered. Conditional tenders quoted by the contractor are liable to be rejected.
- 10) No escalation in the rates will be allowed under any circumstances.
- 11) On receipt of the intimation from the bank of the acceptance of his quotation, the contractor should submit his acceptance within 3 days if the successful contractor/ tenderer fail to undertake the work within 7 days after work allotment, the MMD will be forfeited and acceptance of his tender may be withdrawn.
- The rate quoted in the tenders shall be inclusive of all materials as required and shall be inclusive of all charges of scaffoldings, lifting, tools and plants, freights/ transportation, labour conditions and fluctuations in rates of excise duty, octroi, GST, VAT, Excise Duty, service tax and any other taxes or expenditure of carrying out the
- 13) The Agency is advised to inspect and examine the sites and satisfy himself as to the condition prevailing at sites and its surrounding extent of work, scope and conditions under which the work is to be executed. The contractor shall also satisfy himself about the accessibility to the premises.
- 14) The agency shall submit the offer which satisfies each and every condition laid dawn in this notice, failing which the tender will be liable to be rejected. Conditional bids shall not be considered and will be out rightly rejected in
- 15) Work will be completed within the period of 20 days from the date of issue of tender or work order whichever is earlier. If the work be not completed to the satisfaction of employer within the stipulated period, the contractor will be bound to pay to the Employer a sum equivalent to Rs.2000/- per day subject to ceiling of Max 10% of the accepted contract amount by way of liquidated damages and not as penalty during which the work remains uncommenced or unfinished after expiry of the completion date. The contract may be rescind by giving one week notice incase work is not executed as per specification and as per time schedule given in tender कायालर document.

- 16) The liquidated damages as mentioned in the Notice inviting tender may not be enforced if the contractor applies for extension of time mentioning the genuine reasons for extension. If an extension of time of completion of the work is sought on the grounds of having unavoidable hindrances in his execution or any other ground, the contractor shall apply in writing to the Zonal Manager, Zonal Office BALRAMPUR with full details of the circumstances which is causing such an extension. Extension of time in days will be granted by the bank if it is proved that the contractor is not at fault for extending the work beyond stipulated date of completion. At the decision in this regard taken by the Bank shall be binding to the contractor.
- 17) The successful contractor is bound to carry item of work necessary for completion of job even though the same are not included in the schedule of quantity. Rates of extra item will be derived from quotation. In case the rates do not exist in quotation and extra item is not similar to the quoted item, then the rates will be worked out on actual cost of material and labour, any other expenditure for completing that work plus 15% towards contractors profit and overheads.
- 18) The work shall be carried out in such a way that, there is least disturbance to the staff of Bank. Contractors are required to organize the work in such a way that workings of staff and officers/executives of Office are not affected. Contractor is required to take adequate Care during progress of work to protect belongings. In case any damage, contractors at their own cost shall make the same good.
- The contractor must co-operate with other contractors appointed by the bank so that entire work shall proceed smoothly and to the complete satisfaction of the Bank.
- 20) Contractor will arrange necessary tools and plants for completing own work at their cast. In case of any accident the total responsibility will be on the contractor. Contractors are required to submit time schedule of work. After completion of work, cleaning of floors, walls etc are to be done on daily basis to the satisfaction of Branch Head / engineer-in-charge. After completion of jobs, the site shall be cleared of all rubbish malba /debris etc in all respect and handover the site in proper manner on completion of the work.
- 21) No advance will be paid. Payment will be released on satisfactory completion of job and submission of bills. Retention Money @10% will be deducted from the bill and to be released after twelve months from the data of virtual completion provided no defects is observed during the period.
- 22) In case of non-completion or delay in completion of work or removal of defects in time, the bank shall be free to appoint another agency to get the job done at contractors risk and cost.
- 23) The contractor will attend to all the defects noticed during defect liability period. If the contractor fails to attend the defects these defects will be got rectified by the bank and the expenditure incurred on this account will be recovered from security deposit / retention money.
- 24) The work shall be got approved by the Architect / engineer and the contractor shall rectify any bad workmanship pointed out at any stage and remove from the site all the rejected materials immediately at his own cost.
- 25) The contractor shall acquaint himself with the site conditions making his own arrangements for storing of materials at site, lift, cartage etc. at his own risk and safety.
- 26) The Contractor shall make adequate arrangement for watch and ward of material and shall ensure the safety, breakage and any theft of material fixed or unfixed by him or the other sub contractors. The bank shall not be liable for any sort of loss incurred.
- 27) The contractor shall be responsible for application of labour laws, compensation for injury and accident to person, whether employed by him or his sub-contractor.
- 28) The contractor shall ensure that the workmen employed by him for the execution of work are suitably covered against Workmen Compensation Act and that all liabilities arising out of Workmen's.
- 29) Compensation Act, ESIS and other legislative enactment applicable to such works and workmen shall be to the contactor's account and responsibility.
- 30) Civil, Interior Furnishing and Electrical Works will be carried out as per Bank's standard drawing / specifications and to the entire satisfaction of the bank.
 31) The contractor shall inform the bank.
- 31) The contractor shall inform the bank, well in time, to check measurements of anywork, which is likely to be hidden before covering.
- 32) Income tax at me prevailing rates will be deducted at source from contractor's bill and will be deposited with I.T.O. as per rules.
- 33) Any extra work or item can only be started by contractor after obtaining written approval from the Zonal Office. Item executed without prior approval from the Zonal Office will not be considered for payment.
- 34) The quantities mentioned in the schedule of quantities are approximate. Payment will be made on the actual work done by the contractors. However the contractor should not deviate the quantity without Banks permission.
- The Bank has the right to alter the nature of work and to add or omit any items of work or to have the option of the same carried out departmentally or otherwise and such alterations or variations shall be carried out without prejudices to the contract.
- The Bank has the right to terminate the contact if the contractor abandons the work or fails to commence the work in time, or fails to abide by the terms & conditions of the contract.

I have read and understood all the instructions/conditions given above and I have taken into account the above instructions/conditions while quoting the rates.

Date:

Place:

(Signature of the Contractor) Seal



$SUMMARY\ FOR\ INTERIOR\ FURNISHING\ WORK\ FOR\ RELOCATED\ INDIAN\ BANK\ BRANCH\ AT\ SAIDULLA\ NAGAR-BALRAMPUR$

		AMOUNT (Rs.)
A	SCHEDULE - 'A' (FURNISHING WORK)	<u> </u>
1.0	FALSE CEILING	
2.0	PARTITION WORK	
3.0	DOOR & ACCESSORIES	
4.0	WORKING COUNTER	
5.0	TABLE & FURNITURE	
6.0	CUPBOARDS AND SIDE UNIT	
7.0	OTHER MISC. WORK	
	TOTAL SCHEDULE " A "	
В	SCHEDULE - 'B' (ELECTRICAL WORK)	
I	ELECTRICAL WORK, DB, WIRING ETC	
II	ELECTRICAL WORK & LIGHT FIXTURE & FITTINGS	
	TOTAL SCHEDULE "B "	
С	SCHEDULE - 'C' (LAN & TELEPHONE WORK)	1
1.0	LAN & TELEPHONE WORK	
	TOTAL SCHEDULE "C "	
D	SCHEDULE - 'D' (AC WORK)	=
1.0	AC WORK	
	TOTAL SCHEDULE "D "	
	TOTAL (SCHEDULE - A+B+C+D)	
· · · · · · · · · · · · · · · · · · ·	IF ANY DISCOUNT	
	DISCOUNT AMOUNT	
	GRAND TOTAL	
	NOTE :- GST (WCT) TAX WILL BE EXTRA.	
	Contractor Signature & Seal GST No:-	



A	B.O.Q OF INTERIOR FURNISHING WORK FOR RELOCATED INDIAN BANK BRANCH AT SA SCHEDULE - 'A' (FURNISHING WORK)	AIDULLA	NAGAR-BA	LRAMPUI	R
				T	T
S.NO.	DESCRIPTION CHERENDED FALCE CELLING	UNIT	QTY.	RATE	AMT
1	SUSPENDED FALSE CEILING			-	
1.1	FALSE CEILING (GYPSUM BAORD)				
	Providing and fixing Gypsum false ceiling as per drawing including of providing and fixing G.I. Frame work shall comprise of G.I. perimeter channel (MF-6A) of size 0.50mm thick having one flange of 19.6mm and another flange shall be of size 29.6mm and a web of 26.6mm along with perimeter of ceiling, screw fixed to the beam to the required curvature with nylon sleeves and screws at not exceeding 610mm centers. Then suspending G.I. intermediate channel (MF-7) of size 45mm, 0.9mm thick with two flanges of 15mm each bent to the required curvature by cutting both its flanges. Suitable bracing to be provided where ever the flanges are cut with 0.9mm G.I. Flat and nuts and bolts at specific positions and thereafter at1220mm centers with ceiling angle of width 25mm x 10mm x 0.50mm thick fixed to soffit with G.I. cleats and steel expansion fasteners as per specification of India gypsum at a distance of 2'0" c/c both ways complete with 12.5mm board and all necessary perimeter channels etc. The joints to be properly mended with paper tapes and gypsum compound all complete. The boards are to be jointed and finished which includes filling and finishing the tapered and square edges of the boards with jointing compound and fiber tape suitable for Gypsum board. A layer up to of 3.00mm thickness of Veneer Plaster is applied followed by two coats of topcoat (primer) at the face of board to give smooth seamless finish. 2 or more coats of plastic emulsion paint (roller finish) of approved shade and make shall be applied. The rate should include the full completion of the ceiling. At the time of handing over the site all necessary repairing work to be considered if required. The work to be completed as per specification , approval of the bank. No Drop or design(if any)will be considered as extra measurement it will be considered flat ceiling. (Only plan area to be measured for payment)	Sq.Ft.	495.00		
	measurement it will be considered flat ceiling. (Only plan area to be measured for payment) No extra payment will be made for the cutting of light points, stain glass, cove lighting etc. The measurement will be taken in one level, rate should include the drops also, no extra amount will be paid for the drops.				
1.2	FALSE CEILING (ARMSTRONG CEILINGS – FINE FISSURED MICROLOOK EDGE WITH SILHOUETTE GRID (BLACK REVEAL) Providing and fixing false ceiling system manufactured by M/s. Armstrong World Industries using hot dipped galvanized steel section, rotary stitched main tee of size 15mm x 42 mm web height, having 0.36 mm gauge at every 600 mm centre to centre maximum and rotary stitched cross tee of size 15 mm x 42 mm, having 0.33 mm gauge at every 600 mm. c/c. and wall angle of size 19 x 19 mm., having 0.35 mm gauge fixed to the periphery of the wall. The above grid is suspended at every 600mm c/c. in both directions using 2.0 mm. thick prestraightened GI wire laying FINE FISSURED MICROLOOK WITH SILHOUETTE GRID(BLACK REVEAL) ceiling tiles manufactured by M/s. Armstrong World Industries, of size 600mmx600mmx15mm having NRC 0.55, Light reflectance of >84% (WT), thermal conductivity k = 0.052-0.057 W/m0K, Humidity Resistance of 99%, having Fire Performance CLASS 0 / CLASS 1 (BS 476), surface having 3 coats of white paint with Fine Fissured, back of the tile duly sanded and finished with a coat of protective paint over the formed grid complete.(Branch & ATM).	Sq.Ft.	600.00		2
	TOTAL OF SUSPENDED FALSE CEILING				
2	PARTITIONS WORK				
_	THE TOTAL TOTAL				
2.1	FULL / LOW HEIGHT SOLID PARTITION Full ht. Solid Partition including flush door & strong room partition up to 7' only WITH LOUVRE: Providing and fixing solid partition, the framing shall made out of aluminium hollow section of 65mm x 37mm size 1.5mm thick of JINDAL / INDAL as internal frame structure placed horizontally & vertically at max distance of 2'-0" x 2'-0" center to center. Fixing 6 mm thick commercial ply on both sides with 1.0mm thick laminate on top of approved shade with groove pattern as per instructions of Architect. The rate shall include the cost of providing skirting of 100mm wide lined with 1mm thk laminate and providing & fixing a border at top of 100mm wide lined with 1mm thk laminate complete. Laminate Should be considered up to two or three color combination. The edge beadings with steam	Sq.Ft.	5.00		



	beach wood should be finished with melamine polish if required, frame work above false ceiling done shall not be measured but contractor may factor it while quoting there rates as measurment up to false ceiling lvl				
	The rate inclusive of providing & fixing of required flush door of 37mm thick approx. with 1.0mm th.laminate both side with steem beech wood chowkhat of size 75mm x 65mm approx and Item includes Heavy-duty SS ball bearing butt hinges $100 \times 5.5 \text{ mm}$ (4 Nos. per shutter) with screws etc.The shade of laminate finish to be got approved from Bank. All as per the design and instructions Bank.				
	Note: For the purpose of payment partition shall be measured including the area of door/door frames up to false ceiling heaight.				
	Framework shall be regidly secured to floor, bottom of slab & exisitng walls at 2'-0" c/c with dash fasteners.				
2.2	Single skin partition	Sq.Ft.	290.00		
	As of the above but Providing and fixing single skin partition above false ceiling(where false ceiling is provided only on one side) for a height of up to 600mm or near about soffit of roof using aluminium frame as specified above along with 6mm thick Commercial ply wood lined on only one side and lining with 1mm thk laminate of approved shade and amke along with grooves.				
2.3	Full height Glazed partition manager cabin	Sq.Ft.	185.00		
	Same as of Solid ht. partition, providing 8mm thick Modi/saint Gobin float glass above 1'-0" / 3'-0" & up to 7'-0" fixed with steam beech wood beading of finished size 1 1/2" X 1" all along the edge. All edge-to-edge glass joint to be machine cut and polished and sealed with silicon sealant. joint shall be located strictly as shown in the drawing. All exposed woodwork to be mealamine polished. Item includes frosted/striped/designer glass film of 3m, Avery Dennison or equivalent (basic rate of Flim Rs. 50/ Sq.ft.) on existing glass as per manufacturer's specifications. All as per the design and instruction Bank.	•		-	
0.1					
2.4	Single window Partitions cash cabin Providing and fixing in position Double skin partition 7'-0" height. The framing shall made	Sq.Ft.	100.00		
	out of aluminium hollow section of 65mm x 37mm size 1.5mm thick of JINDAL / INDAL as internal frame structure placed horizontally & vertically at max distance of 2'-0" x 2'-0" center to center. Fixing 6 mm thick commercial ply on both sides with 1 mm thick laminate of approved colour and shade as per approval of the Architect. The partition to include 8 mm. thick Modi Float glass with etching on the sides and back including a door 3'-0" wide as per the approval with all necessary hardware, night latches etc. All exposed edges to be covered with steam beech wood Beading,4mm grooves in places as per design duly melamine polished inclusive of all materials,hardware, night latches, labour, T&P, taxes, levies, etc. completed to the satisfaction of the bank & drawing.				
2.5	Low. Height Semi Glazed Partition	Sq.Ft.	90.00	-	
	Same as above but of Low height as per design including 10mm Toughened glass with edges polished to be used. All other specs are same as of above, Edges of the partition to be covered with 3" X 1.5" Steam beech wood duly melmine polished moulding. 38mm thick flush door: wicket gate also shall be included for a measurement. All as per the design and insturction bank.				
2.6	Front Glazeing In head cash cabin & SWO	Sq.Ft.	30.00		
	Providing & fixing 10mm thick toughened clear float glass to shape for front side of the cash counters including cutting the holes and providing & fixing TW beading polished and tinted to approved shade. (including SWO/Chief Cashier front Glass).				
2.7	Aluminium grill on the ceiling of Cash cabin	Sq.Ft.	70.00		
	TOTAL OF PARTITIONS WORK				
3	DOOR & ACCESSORIES				
2.4					
3.1	Providing and fixing aluminium entrance doors with 12mm floatglass (3M frosted sticker) as/design with top & bottom section of 45 by 90mm, 2mm thick section of hindalco/indal anodized in approved colour with 25 micron anodizing along with SS C shaped handles of kitch or equivalent make along with floor spring of hemco/everite make. The item also includes door lock completed to the satisfaction of the architect	Sq.Ft.	60.00		
	in a set of the set of				

Gonda allost

				1	
3.5	Supplying and fixing of Dorma/GEZE Dline / Hardwyn/Godrej or approved equivalent Door Closer for wooden door for Branch manager, Banking hall, Chief Cashier, Dinning, UPS, Toilet	Nos	5.00		
3.6	Supplying and fixing of mortice door lock of hardwyn make HML-480 Lock Body 304 Stainless Stell. (in BM Cabin , Store room 0. Cash cabin shall be Godrej Night latch.(atm 1 No.)	Nos	4.00		
3.7	Supplying and fixing of door stopper SS Grade 304, HESSF-2C hardwyn make.	Nos	6.00		
	TOTAL OF DOOR & ACCESSORIES				
4	WORKING COUNTER				
4.1	CASH COUNTERS	Rft.	9.00		
	Providing and fixing Chief Cash Counter in split-levels @ 2'-6" (height 750mm) & 18" (1140mm) with 2'-6" & 15" wide each respectively. Upper levels having 12mm thick frosted toughened glass (i/c taxes and transportation). Edges of 18" wide counter shall be 12mm thick frosted toughened glass. Lower tier shall be made of 19 mm thick ply wood finished in 1.5mm thick laminate. Exposed edge having steam beech wood edging of size 1 ½" x 1". Vertical face shall have 12mm thick frosted toughened glass as per requirement of design. All exposed surfaces shall be finished with 1.0mm thick laminate of approved shade and colour. 1 no. prefabricated metal computer key board tray including drawer slides 12.5" x 22" tray with 14" telescopic slides including L – brackets for securing to the table top. Chest of drawers (size 1'-4" x 2'-0" x 2'-5") made of 19mm thick commercial ply wood having three drawers finished with 1.0mm thick Laminate on all sides. Each drawer shall have locking system and 6" long S.S. brushed finished handle, drawer slides etc. of approved make. All exposed edges of ply wood sealed with Steam beech wood beading of size ¼" x ¾". All beading and exposed wood shall be melamine polished and the Internal surfaces shall be .75 mm thick laminate. Item includes readymade metal powder coated CPU trolley, grommet, footrest for each seat. All complete as per approval and instructions of the Architect / employer. The rate also include providing and fixing painting a foot rest using hard wood 100 x 25mm size 1st class seasoned country frame. Payment will be made only on the centerline measurement. The rate shall include the cost of providing skirting of 100mm wide lined with 1.0mm thk laminate and providing & fixing a border at top of 100mm wide lined with 1.0mm thk laminate comlpete. the Internal surfaces shall be .75 mm thick laminate.		5.00		
4.2	RUNNING COUNTER	Rft.	18.50		
	Providing and fixing staff counter/SWO in split-levels @ 2'-6" (750 mm) & 3'1" with 2'-6" (750 mm) & 9" wide each respectively. Upper levels having 1 mm thick laminate with 19 mm thick commercial ply top. Lower tier shall be made of 19mm thick ply wood and finished in 1 mm thick laminate. Working top having steam beech wood edging of size 1 ½" x 1". Vertical face shall have 19 mm thick commercial ply over pine wood framework as per requirement of design. All exposed edges of ply wood sealed with Steam beech wood beading of size ¼" x ¾". All exposed surfaces shall be finished with 1.0mm thick laminate of approved shade. The item includes Chest of drawers (size 1'-4" x 2'-0" x 2'-5") made of 19mm thick commercial ply wood having One drawers at top and a storage cabinet below having shutters of 19mm thick ply wood finished with 1.0mm thick Laminate on all sides. 1 no. prefabricated metal computer key board tray including drawer slides 12.5" x 22" tray with 14" telescopic slides including L – brackets for securing to the table top for each seat. All beading and exposed wood shall be melamine polished and the Internal surfaces shall be .75				
	mm thick laminate. Item includes 1'-3" high 12mm thick toughned glass above upper tier and readymade metal powder coated CPU trolley, grommet, foot rest for each seat. All complete as per approval and instructions of the Architect / employer. The rate also include providing and fixing painting a foot rest using hard wood 100 x 25mm size 1st class seasoned country frame. Payment will be made only on the centerline measurement. The rate shall include the cost of providing skirting of 100mm wide lined with 1.0mm thk laminate and providing & fixing a border at top of 100mm wide lined with 1.0mm thk laminate comlpete.				
	TOTAL OF WORKING COUNTER				
	MADY D. O. DELIDALIMETER				
5	TABLE & FURNITURE				



	Providing and fixing tables made out of 19 mm thick commercial ply over hard wood frame work finished with 1 mm thick laminate of approved shade. Top having steam beech wood edging of size 2" x 1 ¾". 10mm thick clear float glass with beveled edges shall be provided on the finished to 19mm thk Comm.ply wood of approved make cladded with 1mm thk. laminate(color with vertical grain) as per design in all visible areas. All the exposed edges to be covered with wooden steam beech lippings and mouldings duly malamine polish. The drawers to be made out of 19mm thk ply wood with 1.0 mm laminate finish in the front, and bottom to be made out of 6mm plywood and it should play in drawer sliding telescopic channels. The inside of the drawer shall be .75 mm thick laminate. & Table back side wil be 1mm laminate. A leg rest to be provided duly polished made out of 3"x2" Wooden Section.The rate inclusive of providing &fixing wooden cabinet to suit the DVR for size 2'X6"X1'9" or as per the requirements) A shutter to be made by 19mm ply wood cladded with 1.0mm laminate .The necessary locks			
	handles to be provided in each drawers and shutters. $3" \times 1/2"$ wooden skiritng to be provided in all visible areas duly polished. The necessary wire managers(SS) to be provided on the tables and provision for lights to be kept if required in the front of the table. All the exposed areas to be duly malamine polished The work to be completed as per design and approval of the Bank. The table should have key board tray and CPU Trolly to be Modular. All as per the design and instructions Bank the Internal surfaces shall be .75 mm thick laminate.			
5.2	Officer TABLE (Size:- 5'-0" x 2'-6") ht. 2'-6" as per above specification	Nos	0.00	
5.2	without glass top Server TABLE (Size:- 5'-0" x 2'-2") ht. 2'-6" as per above specification	RFT	0.00	
	without glass top		0.00	
	TOTAL OF TABLE & FURNITURE			
6	STORAGE & SIDE UNIT			
6.1	Providing and fixing Side Unit/ Back unit 400 mm depth made out of 19mm ply wood finished with 1.0mm laminate in all exposed areas and top shall be 1 mm thick. The drawers to be made out of 19mm commercial plywood and cladded with 1.0mm laminate and bottom made out of 6mm comm ply duly painted in matching tone and it should play on drawer sliding channels. The shutters to be made out of 19mm commercial ply wood and should play on drawer sliding castors on powder coated channels. The necessary locks, handles, etc to be provided. 3" x1/2 wooden skirting to be provided duly polished as per matching tone all along the visible areas. Inside of the unit shall be .75 mm thick laminate. in matching tone. All the exposed edges of the boards/ply woods to be coverd with woden lippings/mouldings duly polished all complete. The work to be completed as per approval and specification of the Architect. Low HT cabinet	Nos Sq.Ft.	0.00	
6.3	Providing and fixing Full /Low height Cabiner400mm deep made out of 19mm thk plywood finished with 1.0mm laminate in all exposed areas. The Shutter to be made out of 19mm ply wood in the front cladded with 1.0mm laminate(color, vertical grain). and bottom made out of 6mm plywood duly painted in matching tone and shelves 19mm thk comm ply wood to fixed inside storage. The shutters to be made out of 19mm ply wood. The necessary locks, handles, etc to be provided. 3" x1/2 wooden skiritng to be provided duly polished as per matching tone all along the visible areas. Inside of the unit shall be .75 mm thick laminate finish. All the exposed edeges of the boards/plywoods to be coverd with wooden lippings/mouldings duly polished all complete. All as per the design and instructions Bank. Main Electrical Panel Cabinet Providing and fixing of DB Shuttering formed of 12mm thk plywood wood on 12mm thick	Sq.Ft.	35.00	
7	Gypsum board (fire Proof) with finsih as per Item no 1 for inside and out side shutters finished with laminate on outer surface with SS (4Nos) louvre perforation and necessary hardware,hinges etc complete as per details. All as per the design and instructions Bank.Only front face used for measurement only TOTAL OF STORAGE & SIDE UNIT OTHER MISCELLANEOUS ITEMS			
7.1	PIN UP / NOTICE BOARD			
	Providing and fixing soft board with necessary framework with 12mm BWR plywood on top 12 jolly board to be fixed finished with fabric @Rs80 , with necessary mouldings duly	Sq.Ft.	24.00	
7.4	polished along the periferi. All as per the design and instructions Bank.			



	Providing and fixing writing ledge as per design minium 5 ft length made out 19mm comm. board with necessary grove patterns with 1.0mm laminate. 10mm thk machine polished glass to be provided on top of the writing ledge. Small boxes to be made out of 12mm comm. ply to be made on top of the writing ledge finished with 1.0 mm laminate, inside surfaces shall be .75 mm thick laminate. and rate should be included providing fixing of sugestion box & Cheque deposit box as per approval of bank .The work to be completed as per design and approval of the architect.				
7.5	BOXING FOR ROLLING SHUTTER	_			
	WITH ACP FINISH				
	Providing and fixing boxing for the rolling shutters.l. Framing shall consist of Aluminium Sections of 50 mm x 25 mm @ 600mm C/C. Both ways horizontally and vertically on the wall / with Aluminium Sections of 2"x1" as directed by Bank / Architect. This framing would be covered by with 2mm thick "Aluminium Composite Panel". The rate shall inclusive of necessary fixtures and fittings, sealant etc.complete.	Sq.Ft.	80.00		
	Washing as a supply and a supply a sup				
7.6	WOODEN COLUMN PANELLING	Sq.Ft.	0.00		
	Fabricating and fixing wall/column paneling, the framing shall made out of aluminium hollow section of 65mm x 37mm size 1.5mm thick of JINDAL / INDAL at spacing not exceeding 600mm bothways (horizontal and vertical). Paneling framework to be secured to wall surface/column surface.Paneling framework to be clad on one side with 9mm thick ply finished with 1.0mm thk laminate including skirting of 100mm high & 12mm x 12mm groove at skirting level. All as per the design and instructions Bank.				
7.0	Contain Table (ALOU V OLCH)	N	0		
7.8	Customer Table - (4'-0" X 2'-6") Providing and making a table of over all size of top as mentioned above. It shall consist of ¾" thk. Comm. Ply top as per design (double edge on outer edge with 1 1/2" thk half moulding on the edges) supported on ¾" thk. Comm. Ply verticals.supported on wooden base (as designed by the architect). Suitable wooden moulding as architect design with mellamine shall be provided to the edge of the top. All external surfaces to be finished in 1 mm laminate. & the Internal surfaces shall be .75 mm thick laminate.	No	0		
	TOTAL OF OTHER MISCELLANEOUS ITEMS				
	TOTAL OF OTHER MISCELLANEOUS ITEMS				
	GRAND TOTAL FOR FURNISHING (A)				
	* GST EXTRA AS APPLICABLE				
	TO A THE STATE OF	1		L	

В	SCHEDULE - 'B' (ELECTRICAL WORK)				
SL No	PARTICULARS	UNIT	QTY	RATE	AMT
1	ELECTRICAL WIRING & EARTHING				
, 1.1	Supply, laying, connection & testing of light, fan point, wiring by 2x1.5mmsq(2x3/.029) +1x1mmsq PVC insulated, multistrand single core copper conductor FRLS wire maintaining the colour code as per direction in PVC conduite of 20mm with ISI mark 1.5mm thickness to conceal in wall partition mending good the damage, complete with PVC circular box, bend to be done as per drawaing including 3 point ceiling rows wherever required GI saddle to be used for fixing, metal flexiable/PVC flexiable pipe may use if requied in partition wall. All PVC pipes should be with ISI mark. No joints will be allowed inside pipe, light, fan & plug point complete with modular type switch plate & MS box . rate including the main circuite line 2x2.5mmsq+1x1.5mmsq earth PVc insulated Cu. Wire from DB to switch board , maintaining the colour code. Circuite line for lighting switch board & 6Amps plug board are to be drawn from lighting DB to Lighting board & plug point board (independent), 6/16 Amps plug point line are to be draw from power DB.as per DBschedule /SLD				



a)	1 light by 1 switch	Nos.	32	
b)	2 light by 1 switch	Nos.	17	
c)	3 light by 1 switch	Nos.	0	
e)	Ceiling fan point with step type electronic regulator	No	0	
f)	Same as above, but for exhaust fan excluding regulator.	No	0	
g)	Same as above 5A Point in the switchboard itself. (for branch 4 No & ATM 1 No)	No	7	
h)	same as above Wiring for call-bell point including buzzer	No	1	
i)	Wiring (2x2.5mmsq+1x1.5mmsq from power DBs) for independant 6A multi pin socket at walls along with 6A modular type switches board housed in painted MS box (upto 3 independent plug points can be taken in one circuit). For wall Fan	No	10	
1.2	Supply and installation of modular type 2 nos 6A & multi pin sockets with 2 nos 6 Amp one way switch housed in MS box to be fixed in partitions or concealed in wall. The box shall be painted with 2 coats of enamel paint over a coat of red oxide primer including wiring for Raw power socket outlet using 2 R runs of 2.50 Sqmm and single run of 1.5 sqmm PVC insulated multi stranded single core copper conductor FRLS wire in 20mm PVC conduit to be laid in floor, partitions, etc. complete with all accessories (looping 2 sets of 2x6A socket outlet in one circuit-from DB) (Raw power). for counter (Each counter 1 Nos +BM :2 Nos, ATM 1No:,Pantry 1No.:)	No	7	
1.3	Supply and installation modular type 16A, 5-pin socket with 16A one way switch housed in MS box to be fixed in partitions or concealed in wall. The box shall be painted with 2 coats of enamel paint over a coat of red oxide primer , the rate shall include wiring fusing 2R 4.0 sqmm & single run of 2.5 sqmm PVC insulated multi stranded single core copper conductor FRLS wire in 25mm PVC conduit to be laid in floor, partitions, etc complete with all accessories (for line printer : or optional).(upto 2 independent plug points can be taken in one circuit) C.C :1No. BM.;1 No.: Alternative counter 2No + Banking Hall 1 No+ Pantry 1No ,ATM :1No)	Nos.	9	
1.4	Supply and installation of power supply disconnection arrangement for strong room consisting of 1 no 10A DP MCB housed in manufacturer's powder coated MS box to be fixed inside the strong room and connected with 1 no 3-pin metal clad plug with 2 metre long 3 core 2.5 sqmm PVC insulated flexible copper conductor cable.	Set	1.00	
1.5 (a)	Acs electrification:- Supply and fixing 25 Amps 3-pin modular socket with 25 Amp one way switch with indicator (near AC indoor unit) housed in manufacturers MS powder coated box to be concealed in wall includding Wiring using 2R4.0 sqmm & single run of 2.5 sqmm PVC insulated multi stranded single core copper conductor FRLS wire in 25mm PVC conduit to be laid in floor, partitions, etc complete with all accessories. (for split AC units) -(from Stabilzer to IDU)Supply. (2 Nos for ATM), Stablizer to be installed in the panel room.	Nos	4	



(b)	Supply and fixing 25 Amp - 3 pin metal clad socket with plug controlled by a 25 Amp SP MCB (for				
	Ac wall mounted stabilizers) housed in manufacturers MS powder coated box to be concealed in wall including Wiring using 2R 4.0 sqmm & single run of 2.5 sqmm PVC insulated multi stranded single core copper conductor FRLS wire in 25mm PVC conduit to be laid in floor, partitions, etc complete with all accessories. (for split AC units) from AC DB to Stablizer (2 Nos for ATM)	Nos	4		
2	LAYING OF CABLE :			-	
2.1	Supply laying fixing main power with 50mm sq 3.5 core PVC.insulated,PVC sheated Alu.Conductor, 1100 v. grade armoured cable complete with 02 nos 8 SWG bear Gl.wire as running earth .(Meter panel to Main Panel & Dgset to Main Panel)	Mts.	5		
2.2	End termination of 50mmsq 3.5 Core armoured cable,complete with brass cable gland , Alu. Lug, PVC tape.	Nos	4		
2.3	- Do - 3.5 x 16 sqmm with 02 nos 8 SWG bear Gl.wire as running earth. for Light D.B	Mts	25		
2.4	- Do - 3.5 x 25 sqmmth with 02 nos 8 SWG bear Gl.wire as running earth. for POWER & A.C D.B , UPS & ATM	Mts	25		
2.5	- Do - termination of 25 & 16 Sqmm 3.5 Core	Nos	8		
2.5	DO TERMINATOR DE LA TOSAMINIO SE COLO	1403	0		
3	Out door type glow sign board wiring :-				
3.1	Supply laying of main line with 2x2.5 +1x1.5 mmsq through MS conduite from main panal to glow sign board.	Mts	25		
3.2	Supply installation of 16 amps DP MCB at main entrance Glow sign board & With Electronic timer as required.	Set	1		
4	EARTHING STATION:				
(i)	Earthing installation as per I.E. rule conforming	Set	2		
	Supply, Installation, Testing and Commissioning of Maintenance Free Earthing system made up of				
	copperbonded rod of 10 feet length,23 mm dia. (Minimum copper bonding shall be 0.25mm) along with Rod-toConductor connectors, Earth enhancement material, Pit Cover and other				
	accessories as required and as per specification and other applicable codes (include chamber for earthing, Earthing certificate to be submitted along with the bill).				
(;:)					
(ii)	Supply laying 2x8SWG copper bear wire from earth spike to main panal.(Electrolite wire)	Mts	20		
5	MAIN ELECTRICAL DISTRIBUTION	14163			-
	I MAIN ELECTRICAL DISTRIBUTION				



	1 1	i	1	
Supply, fabricating, assembling, internal-connection, testing & connecting with incomming, out			8	
going power cables & lines as required to complete the job of cubical type electrical panal made from 14SWG CRC. M.S. sheet with proper earthing terminal(Nut- bolt &washer) 02 No.outside of				
panal, same nut- bolt to tighten with internal earth busbar of panal situated inside loose wire				
box(on top portion of panel) On top side of panel cable entry arragement to be done for				
incomming & out going of lines. Painting powder coating electrical grey/ seimensgrey to be				
done.one 6"x4" enamal type 440Volt Danger board to fix up on main panal bus-bar cover,				
components are as follows:-All switches are front handle operated & all MCB knob should be				
visual, all component to provide in separate compartment only DBs in one compartment. Incomer - 100A 4P MCCB 25Ka with adjustable thermal & Magnetic trip unit -1 Nos				
Incomer - 100A 4F Mices 25Ka With adjustable thermal & Magnetic trip diffe 1 Nos				
OUTGOINGS -				
001001103-	-			
63 Amps 4 pole MCB. = 04 Nos.(AC & Power DB,ATM, UPS,spare)				
40 Amp 4 Pole MCB :2 nos (Lighting DB,Spare) 25 Amps DP				
MCB = 02 Nos. (sign board , Fire Alarm) Amps Meter				
0-100 Amps with 3 Nos. CT & selector switch 96x96mm 01 Set (Changeover should be				
ON-LOAD type.)				
100Amps 4 pole Cu. Bus Bar. 01 Set. 100Amps 4 pole Change over switch, 01 No. 100 Amps FP MCCB 25KA as Gen				
Change over switch. 01 No. 100 Amps FP MCCB 25KA as Gen - Set main incoming 01 NO.				
Section meeting of the				
Volt meter 0-500volt A.C. 50 Hz.96x96mm with selector switch. AE make.n 01 Set				
20mmdia LED indicator lamp 03 Nos.				
02 Amps Sliding Fuse. 06 Set.				
150x100mm enamal Danger board 440 volt.				
(to set on bus bar cover). 01 No.				
Cable entry from top & bottom - removable gland plates (bottom at 2 points) c/w powder coated				
Grey paint (two coats) with name labels for all incoming & outgoing feeders. The panel shall be				
complete in all respects including all accessories such as earthing bus, Air ventilators, lifting hooks	Set	1		
etc.				
POWER DB & AC DB. Make standard/Legrand/ABB ,Double door				
6 way TPN MCB DB with TP MCB as incoming				
63 TP&N MCB as main				
OS TEAT PRODUCTION				
16Amps SP MCB - 8 Nos (Ac :3 Nos + 2X6amp : 4Nos and 1Nos spare) +32AMPS SP X10 NOS. (Ac				
3 Nos+15 Amp: 6 Nos, 1No Spare)	-			
5.2 including Neutral Bar. 01 Set	Set	1		
	-			
LIGHTING DB Make standard/Legrand/ABB	-			
6 way TPN MCB DB with TP MCB as incoming	-			
63A TP&N MCB as main				
5.3 32 AMPS DB MCB 1No: For Strong room)	1			

Gonda allosi

16 Amps SP MCR - 03 Nos + /RM +Toilet\ oach 1No + 1No spara			1	I
12 Amps SP MCB - 12 Nos. (Hall - 4Nos + Store room 1 No +Exteranl Lighting 1No.:+ Ups 1No + wall Fan 3 Nos.2 No spare)				
Including Neutral Bar. 01 Set	Set	1		
S/F of 3 nos. 100Amps Kit kat set link type with heavy duty neutral link and making its connection from electronic meter c/w wooden board etc.	Set	1	,	
LIDS SYSTEM (Decemb)				
UPS Main DB Supply, erection, testing and commissioning of three phase 4 WAY, TPN MCB DB double door type with "C" Curve MCBs, IP 42 powder coated for UPS with 63A 4P MCBs – 1No as INCOMER 32A TP MCBs – 3 Nos. as OUTGOING (UPS :2Nos and 1 set ,: Spare Including all interconnections & accessories etc Make standard/Legrand/ABB	Nos	1	-	
Supply & Fixing of 32A DP MCB in 2way SPN Db IP 20 metallic directly on wall Raw power Incoming & OutGoing supply for UPS (Branch :2 Nos)	Nos	2		
UPS DB-1 & 2 combined				
12 Way SPN MCB DB with 'C" curve MCBs. Incoming: 2 No. 40A DP MCB Outgoing: 8 Nos 6/10A (BM: 1+1 Nos with lighting: Server & Data Rack (1+1) Nos:C.C 2Nos with lighting: counter: 2 Nos) SPO MCBs Make standard/Legrand/ABB. Repective UPS lighting to be connected.(BM,C.C,Banking hall 2Nos) or as per SLD	Nos	1		
Supply and installation of modular type 3 nos 6A multi pin sockets with 2 nos 6A one way switch with indicator housed in MS box to be fixed in partitions or concealed in wall. The box shall be painted with 2 coats of enamel paint over a coat of red oxide primer including making connections complete the rate inclusive of Supplying and running of 3 runs of 2.5 sq.mm UPS DB's to individual powerstation through .(looping 2 sets of 3X6 A socket outlet in one circuit / or as per SLD the following size of 660 volts grade, Finolex brand PVC insulated wire (For UPS point only).(For B.M,C.C,Sever each 2Nos.) +5 Nos for Counter+Rack 1Nos)	Nos	9.00		
Supply and Installation of Moduler type 2 X 20A plug & socket housed in for UPS output control (Branch 2 Nos & ATM 1No.)	Nos	3.00		
Supply & Laying of 2 runs of 4.0 Sqmm and 1 run of 2.5 sqmm, PVC insulated, single core, multistranded copper conductor cable in suitable rigid / flexible metal conduitfrom 3 KVA UPS to UPS DB	mtr	20.00		
sub total I				
ELECTRICAL FITTINGS (S/I/T/C	-		-	-
Supply and Installation Recess mounted 2'-0"X2'-0" watt ,38 W LED FULL GLOW Philips MAKE . Light should be fixed through SS threaded bolt tighted the upper end on ceiling using anchor bolt and lower end on Light fitting with nut and bolt (RC380B G2 LED35S-6500/4000 PSU OD WH)PHILIPS/WIPRO MAKE	Nos.	10		
	Including Neutral Bar. 01 Set S/F of 3 nos. 100Amps Kit kat set link type with heavy duty neutral link and making its connection from electronic meter c/w wooden board etc. UPS SYSTEM (Branch) UPS Main DB Supply, recetion, testing and commissioning of three phase 4 WAY, TPN MCB DB double door type with "C" Curve MCBs, IP 42 powder coated for UPS with 63A 4P MCBs – 1No as INCOMER 32A TP MCBs – 3 Nos. as OUTGOING (UPS:2Nos and 1 set Spare Including all interconnections & accessories etc Make standard/Legrand/ABB Supply & Fixing of 32A DP MCB in 2way SPN Db IP 20 metallic directly on wall Raw power incoming & OutGoing supply for UPS (Branch:2 Nos) UPS DB-1 & 2 combined 12 Way SPN MCB DB with "C" curve MCBs. Incoming: 2 No. 40A DP MCB Outgoing: 8 Nos 6/10A (BM: 1+1 Nos with lighting: Server & Data Rack (1+1) Nos:C.C 2Nos with lighting; counter? 2 Nos) SPO MCBs Make standard/Legrand/ABB. Repective UPS lighting to be connected.(BM.C.C.Banking hall 2Nos) or as per SLD Supply and installation of modular type 3 nos 6A multi pin sockets with 2 nos 6A one way switch with indicator housed in MS box to be fixed in partitions or concealed in wall. The box shall be painted with 2 coats of remanel paint over a coat of red oxide primer including making connections complete the rate inclusive of Supplying and running of 3 runs of 2.5 sq.mm UPS DB s to individual powerstation through .(looping 2 sets of 3X6 A socket outlet in one circuit / or as per SLD the following size of 660 volts grade, Finolex brand PVC insulated wire (For UPS point only).(For B.M.C.C.Sever each 2Nos.) +5 Nos for Counter+Rack 1Nos) Supply & Laying of 2 runs of 4.0 Sqmm and 1 run of 2.5 sqmm, PVC insulated, single core, multistranded copper conductor cable in suitable rigid / flexible metal conduitfrom 3 KVA UPS to UPS DB sub total I ELECTRICAL FITTINGS (S/VT/C	12 Amps SP MCB - 12 Nos. (Hall - 4Nos + Store room 1 No + Exterani Lighting 1No.:+ Ups 1No + wall Fan 3 Nos.2 No spare) Including Neutral Bar. O1 Set S/F of 3 nos. 100Amps kit kat set link type with heavy duty neutral link and making its connection from electronic meter c/w wooden board etc. Set UPS SYSTEM (Branch) UPS Main DB Supply, erection, testing and commissioning of three phase 4 WAY, TPN INCB DB double door type with "C" Curve MCBs, IP 42 powder coated for UPS with 63A 4P MCBs - 1No as INCOMER 32A TP MCBs - 3 Nos. as OUTGOING (UPS: 2Nos and 1 set .: Spare including all interconnections & accessories etc Make standard/Legrand/ABB Nos Supply & Fixing of 32A DP MCB in 2way SPN Db IP 20 metallic directly on wall Raw power incoming & Outgoing; 8 Nos 6/10A (BM: 1+1 Nos with lighting: Server & Data Rack (1+1) Nos:-C.C 2Nos with lighting: counter : 2 Nos) SPO MCBs Make standard/Legrand/ABB. Repective UPS lighting to be connected.[MB.C.C.Baning hall 2Nos] or as per SLD Supply and installation of modular type 3 nos 6A multi pin sockets with 2 nos 6A one way switch with indicator housed in MS box to be fixed in partitions or concealed in wall. The box shall be painted with 2 coats of fename paint over a coat of red oxide primer including making connections complete the rate inclusive of Supplying and running of 3 runs of 2.5 sqmm UPS DB's to individual powerstation through. (looping 2 sets of 3X6 A socket outlet in one circuit / or as per SLD the following size of 660 volts grade, Finolex brand PVC insulated wire (For UPS point only). (For B.M.C.C.Sever each 2Nos.) +5 Nos for Counter+Rack 1Nos) Supply & Lanying of 7 runs of 4.0 Sqmm and 1 run of 2.5 sqmm, PVC insulated, single core, multistranded copper conductor cable in suitable rigid / flexible metal conduitfrom 3 KVA UPS to UPS DB Supply and installation Recess mounted 2'-0"X2'-0" watt, 38 W LED FULL GLOW Phillips MAKE . Light should be fixed through SS threaded bolt tighted the upper end on ceiling using anchor bolt	22 Amps SP MC8 - 12 Nos. (Hall - 4Nos + Store room 1 No + Exteranl Lighting 1No.:+ Ups 1No + wall Fan 3 Nos 2 No spare) Including Neutral Bar. 01 Set Set 1 Set 1 Set 1 Set 1 SF of 3 nos. 100Amps Kit kat set link type with heavy duty neutral link and making its connection from electronic meter c/w wooden board etc. Set 1 UPS SYSTEM (Branch) UPS Main DB Supply, erection, testing and commissioning of three phase 4 WAY, TPN MC8 DB double door type with "C" Curve MC8s, IP 42 powder coated for UPS with 63A 4P MC8s - 1 Nos. as OUTGOING (UPS:2Nos and 1 set; Spare Including all interconnections & accessories etc Make standard/Legrand/ABB Nos 1 Supply & Eiking of 32A DP MC8 in 2way SPN Db IP 20 metallic directly on wall Raw power Incoming & Outgoing; 8 Nos 67/DA (BM: 1-1 Nos with lighting; counter : 2 Nos 57/DA (BM: 1-1 Nos M: 1-1 Nos M: 2 Nos 57/DA (BM: 1-1 Nos M:	22 Amps SP MCB - 12 Nos. (Hall - 4Nos + Store room 1 No + Exterant Lighting 1No.:+ Ups 1No + wall Fan 3 Nos 2 No spare) Including Neutral Bar. 0.1 Set 1 Set 1 Set 1 Set 1 Set 1 Set 1 Set 3 nos. 100Amps Kit kat set link type with heavy duty neutral link and making its connection from electronic meter c/w wooden board etc. Set 1 UPS SYSTEM. (Branch) UPS Main DB Supply, excetsion, testing and commissioning of three phase 4 WAY, TPN MCB DB double don'type with "C" Curve MCBs, in 24 powder coated for UPS with 32A F MCBs-3 Nos. as OUTGOING (UPS : 2Nos and 1 set ; Spare including all interconnections & accessories etc Make standard/Legrand/ABB Nos 1 Supply & Fixing of 32A DP MCB in 2way SPN Db IP 20 metallic directly on wall Raw power incoming & Outgoing : 8 Nos 6/10A (BM: 1-1 Nos with lighting; 2 No. 40A DP MCB Outgoing : 8 Nos 6/10A (BM: 1-1 Nos with lighting; 1 Server & Data Rack (1-1) Nos:C.C.2Nos with lighting; counter: 2 Nos) SPO MCBs Make standard/Legrand/ABB. Repective UPS lighting to be connected, (BM.C.C.Banking hall 2Nos) or as per SLD Supply and installation of modular type 3 nos 6A multi pin sockes with 2 nos 6A one way switch with indicator housed in M5 box to be fixed in partitions or concealed in wall. The box shall be painted with 2 coals of enamed paint over a coat of red oxide primer including making connections complete the rate inclusive of supplying and running of 3 runs of 2.5 scmm UPS DB's to individual powerstation through, (looping 2 sets of 3KA socket outlet in one circuit, for as per SLD the followings see of Box of by stage fromex translet with 1 spinal set of the power of the powe



8.3	SQUARE SHAPE DOWNLIGHTER - !NTEGRA 15W, 3000K, LHEBGTP5Z1W015, PHILIPS Razor/WIPRO MAKE	Nos.	20		
8.4	TUBELIGHT - TITANIA SLEEK NEW LED TUBELIGHT 36 W, PHILIPS/WIPRO MAKE.	Nos	0		
8.5	HANGING LIGHT - LHECDOL5PW1W040 (40WATTS), PHILIPS/WIPRO MAKE	NOS.	1		
8.6	150 mm dia Heavy Duty Exhust fan 230 voltA.C.(Havells / Crompton make).(UPS & Toilet)	Nos	0		
8.7	Wall mountaing fan 400 mm dia 230 volt A.C. PHILIPS/WIPRO MAKE	Nos.	10		
8.8	Supply of Ceiling fan with 1200mm sweep, double ball bearing motor, capacitor, three MS blades die cast Al housing in stove enameled white with, suspension rod including all accessories of approved make.(5 star rated) (ORIENT/KHAITAN).(UPS,Strong room & Store room)	Nos.	0		
	SUB TOTAL				
	TOTAL FOR ELECTRICAL WORK (B)				
С	SCHEDULE - 'C' (LAN & TELEPHONE WORK)				
S.NO.	DESCRIPTION	UNIT	QTY.	RATE	AMOUNT
2.0	DATA SYSTEM - CONDUITING & CABLING		-		
2.0	Wiring for computer networking from I/O hub to computer workstation with UTP Cat-6 computer cable including providing ferrules at both ends and termination at both ends including providing & fixing frame for with shutter, RJ 45 outlet, faceplate and mounting box complete of modular type, This work includes providing PVC conduits (1/2", 3/4" size or as required0 in chases from the I/O hub to the point. The cost includes testing, commissioning etc complete. Note: Do not run more than 3 wire in single pipe & should be concealed. (Server,BM,CC & ATM each 2Nos and counter 5Nos)	Nos.	9		0
2.2					
2.3	Supply of Cat - 6 D-Link patch cord 7' 0" (ATM 1No)	Nos.	9		0
2.4	Supply of Cat - 6 D-Link patch cord 3' 0"(ATM 2No)	Nos.	9	-	0
2.5	Supply & fixing 24 Port Jack Panel Make:-D-Link 19" Rack 9U with Glass Door , Locking system Make: APW	Nos.	0	-	0
2.6	24PORT 10/100Mbps Switch	Nos.	0		0
2.1					
	GRAND TOTAL FOR LAN & TELEPHONE (C)				0
	TOTAL		-		
			<u> </u>		
	GRAND TOTAL-B+C+D		1		1

