



**INDIAN BANK**  
**BRANCH- RISHIKESH (ERENOVATION WORKS)**  
**DATA CABLING WORKS (Branch & ATM)**  
**BILL OF QUANTITIES (BOQ) AND SPECIFICATIONS**

S.NO.	ITEM DESCRIPTION	QTY	UNIT	RATE	AMOUNT (Rs.)
<b>A:-</b>	<b>DATA CABLING WORKS:</b>				
1.0	Providing and laying UTP Cat-6 cable from the server panel to each destination point, using D-LINK make cable, including all required materials, labour, tools, plants, accessories, dressing, testing, and commissioning, complete in all respects.	300.00	RMT		
2.0	Providing and fixing in position 16-port 10/100 Mbps Ethernet switch of D-LINK make, including all required materials, accessories, labour, mounting, interconnections, testing, and commissioning, complete in all respects.	0.00	Nos.		
3.0	Providing and fixing in position 24-port jack (patch) panel of D-LINK make, including all required materials, accessories, labour, mounting, termination, testing, and commissioning, complete in all respects.	0.00	Nos.		
4.0	Providing and fixing in position 19" floor/wall mountable network rack of 9U height, of approved make ( <b>D-LINK / NETRACK</b> ), with toughened glass front door, complete with locking arrangement, side panels, cable entry provision, minimum one cooling fan, 6-socket power strip, mounting hardware, accessories, labour, installation, testing, and commissioning, complete in all respects.	0.00	Nos.		
5.0	Providing and fixing in position information outlet with dual plate, comprising two Cat-6 keystone jacks, face plate and flush/surface mounted back box, of approved make ( <b>D-LINK / Legrand</b> ), including all required accessories, terminations, labours, installation, testing, and commissioning, complete in all respects.	0.00	Nos.		
6.0	Providing and fixing in position 7' long mounting pole/bracket for network equipment/access point, of <b>D-LINK</b> make, suitable for wall/ceiling installation, including base plate, clamps, fasteners, all required accessories, labour, installation, alignment, and fixing arrangements, complete in all respects.	10.00	Nos.		
7.0	Providing and fixing in position 3' long mounting pole/bracket for network equipment/access point, of <b>D-LINK</b> make, suitable for wall/ceiling installation, including base plate, clamps, fasteners, all required accessories, labour, installation, alignment, and fixing arrangements, complete in all respects.	10.00	Nos.		
		<b>TOTAL C/F</b>			

S.NO.	ITEM DESCRIPTION	QTY	UNIT	RATE	AMOUNT (Rs.)
		TOTAL B/F			
8.0	Providing and laying in position 25 mm dia <b>Medium-duty</b> PVC conduit for Cat-6 cables, laid concealed in wall/ceiling or on surface as required, including bends, couplers, junction boxes, inspection boxes, clamps, saddles, fixing hardware, labour, chasing, making good, installation, testing, and commissioning, complete in all respects.	150.00	RMT		
	TOTAL FOR UPS & DATA CABLING			Rs.	
ABSTRACT COST SUMMARY					
	TOTAL FOR DATA CABLING WORKS:			Rs.	
	TOTAL BEFORE GST			Rs.	
	ADD: GST 18%			Rs.	
	TOTAL AFTER GST			Rs.	
			SAY	Rs.	
Amount in words: Rupees					
<b>Contractor's Under taking:</b> 1- I/my repesantaive have inspected the said Branch premisess personally. 2- I have read and understand all the specifications and terms & conditions properly.					
		APPROVED BY			
	Contractor's Sign and Stamp	ZO: INDIAN BANK, DEHRADUN			