



**FGM Office, Lucknow, 1stFloor, New Building, Hazaratganj,  
Lucknow-226001**

**FINANCIAL BID (FURNISHING WORKS)**

**FOR**

**PROPOSED REPAIR & RENOVATION OF HOSTEL ROOMS, RELATED CIVIL WORKS ALONG WITH NECESSARY  
INFRASTRUCTURE, INTERIOR WORKS EXTERNAL PAINTING, WATER PROOFING, ELECTRICAL WORKS, AIR-  
CONDITIONING WORKS, REPLACEMENT OF LIFT (1 NO) IN  
STAFF COLLEGE, LUCKNOW CAMPUS AT SECTOR No.:485-486-487, SECTOR 21, INDIRA NAGAR, LUCKNOW- 226016.**

Ref.No:TENDER ID.: FGM/LUC/EST/STC/2025-26 -01  
Date : 27.02.2026

Name of the contractor:

.....  
.....  
.....

ARCHITECT / CONSULTANT					
SANDEEP GOVALKAR DESIGN ASSOCIATES				DATE:	
CLIENT : INDIAN BANK					
PROJECT: - PROPOSED FURNISHING & RENOVATION WORKS FOR INDIAN BANK PREMISES AT LUCKNOW					
BILL OF QUANTITIES – CIVIL AND INTERIOR FURNISHING WORKS					
Sr.	Particulars	Qty.	Unit	Rate (Rs.)	Amount (Rs.)
<b>FURNISHING WORKS</b>					
<b>NOTE : IN CASE OF MASS PRODUCTION OF ITEMS TO BE MADE THE VENDOR MUST Prototype of sample to be provided for approval). ALL THE MATERIALS MUST BE GET APPROVED BY ARCHITECT &amp; BANK ENGINEER BEFORE EXECUTION OF WORK</b>					
<b>A FALSE CEILING</b>					
1	Providing and fixing suspended gypsum flat / curved and coffered false ceiling (including coves & bands) of 12mm gypsum sheet with c/c 600mm frame work, which includes providing and fixing g.i perimeter channels of size 0.55mm thick having one flange of 20mm and another flange of 30mm and a web of 27mm along with perimeter of ceiling screws fixed to brick wall/ partition with the help of nylon sleeves and screws at 600mm centre then suspending g.i intermediate channels of size 45mmx0.9mm thick with 2 flange of 15mm each from the soffit with g.i and steel expansion fastener only, "fastener" shall be used for ceiling support only. Ceiling section of .055mm thickness having knurled verb of 51.5mm and two flanges of 26mm each with lips of 10.5mm are then fixed to the intermediate channel with the help of connecting clips and in direction perpendicular to the intermediate channel at 457mm centres, 12.5 tapered edge gypsum board( conforming to is2095-1982) is then screws fixed to ceiling section with 25mm dry wait at 230mm centres, additional support for ac grill shall be fixed as per instruction and ac plan/section/layout. *screw fixing is done mechanically with screw driver of drilling machine with suitable attachment. The board are to be joint and finished so as to have a flush look, which includes filling and finishing the tapered and square edges of the board with jointing compound, paper tape. Note:- for light fittings, grills diffusers and cut-outs, speakers , fire detectors etc have to be made with the frame of perimeter channels of size 20x27x30mm and of 0.54mm thick ,supported suitable as per direction of architect ,electrical and ac consultant and as per the details shown in the drawing / views without additional payments.	400.00	SMT		
2	In position <b>12mm thk Armstrong (fine fissured -rh 99)false ceiling system</b> including manufacturer's Specifications with supporting suspension system and making provision for electrical fittings and air conditioning diffuser, grills etc. As required in different levels/heights/patterns and directed by architect.(in Training & Conference/ Meeting rooms)	500.00	SMT		
3	<b>TechZone ceiling systems</b> to organise lighting, HVAC grilles(if any), into 100mm and 150mm wide technical zones. A range of compatible fixtures from approved brand to be prequalified for fit and finish with a clean, monolithic look using standard ceiling panels and suspension systems as per manufacturer's instructions / Specifications. (Make: Armstrong or Approved Equivalent) Panel Size (Width x Length): 24" x 24" or 24" x 48" as per design Colour: White, Feldspar-dark brown (MFS), Fossil- light brown (MFL) Edge: Square Regular 9/16 Thickness: 1" Acoustics: 0.85 NRC / 35 CAC / 170 AC Sound Absorption (NRC) - 0.85 Sound Blocking (CAC) - Up to 39 Articulation Class (AC) - 170 Light Reflectance - 85% Recycled Content - 76% Sag/Humidity Resistance - HUMIGUARD Plus Materials - Mineral Fibre Fire Performance - Class A (25/450), Class A (UL) Disinfect ability - Fog Durability - Soil Resistance, Impact Resistance, Scratch Resistance, Scrub ability, Wash ability	47.77	SMT		

<b>BILL OF QUANTITIES – CIVIL AND INTERIOR FURNISHING WORKS</b>					
<b>Sr.</b>	<b>Particulars</b>	<b>Qty.</b>	<b>Unit</b>	<b>Rate (Rs.)</b>	<b>Amount (Rs.)</b>
4	<p><b>VOX ceiling installation</b> consist of standard dimensions of 300 mm (approx. 1 ft) width by 2700 mm (9 ft) length, a thickness of around 1.2 mm having a quick-click system for easy fitting of waterproof polymer panels, using as per design special J-Trims, T-Trims, and H-Trims for seamless edges, hidden lighting and concealed wiring, a maintenance-free, ventilated solution for interiors ceiling, with wood-look &amp; plain colours for a modern finish as per design combination.</p> <p>General Installation Steps: Ensure the surface is ready, potentially setting up a frame with support structure.</p> <ol style="list-style-type: none"> <li>1. Start with Trims: Install J-Trims and T-Trims around the perimeter to define edges and create channels.</li> <li>2. Panel Installation: <ol style="list-style-type: none"> <li>1. Attach the first panel, often angled or locked into the trim.</li> <li>2. Install subsequent panels by clicking them into the previous one and securing them to the frame/trim.</li> <li>3. Use H-Trims for straight joins or J-Trims for corner transitions.</li> <li>3. Corner Finishes: Panels can be fitted in a straight pattern or a chevron (angled) pattern for corners, using specific trims as shown in design pattern.</li> <li>4. Lighting: Integrate lighting points as per lighting scheme.</li> <li>5. Final Touches: Install any flashing or final trims to seal edges and complete the look.</li> </ol> </li> </ol>	60.00	SMT		
5	<p><b>Rafters False ceiling wood finish</b> as approved make:</p> <ul style="list-style-type: none"> <li>• Installation: Ceiling panels to be installed using a suspended grid system (drop ceiling) as per manufacturer's specifications.</li> </ul> <p>WPC rafters size 100 mm depth x 60 mm wide x 2900 mm length consist of metal suspended hangs fixed to the slab with anchor fastener &amp; G.I. metal keel to place rafter @ 100 mm c/c complete</p>	50.00	SMT		
6	<p><b>Semicircular arched at entrance porch</b> using pop ceiling with moulding (classic type) vaulted/domed effect with hidden cove lights &amp; chandelier provision for sophisticated look.(cove lights &amp; chandeliers to be installed by electrical contractor) . The work includes cove arches, layered design of multiple pop layers with decorative moulding o intricate shape with skilled execution for precision etc. (at entrance porch canopy as per design given by architect)</p>	50.00	SMT		
<b>C FIXED FURNITURES &amp; CARPENTRY WORKS</b>					
<b>1 PARTITIONS AND PANELLING WORKS</b>					
<b>PANELLING ON WALLS / COLUMNS IN LAMINATED FINISH</b>					
1.1	<p>Providing and fixing panelling for walls, columns etc. Made out of 2" x 1" x 1.2mm thk aluminium tubular frame work at every 2' x 2' c/c, covered with 8 mm thk. Mr ply finished with 1.00 mm. Thk. Sued /glossy/ matt (as approved) laminate/ wall paper of approved shade / make etc. All the exposed wooden /unfinished surfaces to be painted/polished with a shade matching approved laminate as specified .complete as per architect's instructions.</p>	250.00	SMT		
1.2	<p>Providing and fixing 2" x 1" x 1.2mm thk aluminium tubular frame 2'x2' c/c bothways,skinning with mr grade 8mm thk ply and 9mm thk approved polyester eco acoustic panel, as per pattern to give acoustic treatment on walls as per instruction of the architect/engineer in charge (area - conference room)</p>	25.00	SMT		
1.3	<p>Providing and fixing panelling for walls, columns etc. Made out of 2" x 1" x 1.2mm thk aluminium tubular frame work at every 2'x2' c/c, covered with 8 mm thk. Marine ply finished with wpc grooved panels (as approved design and sizes) approved shade / make etc. All the exposed / unfinished surfaces to be polished with approved shade as specified. Complete as per architect's instructions.</p>	45.00	SMT		
<b>2 PARTITIONS : FULLY/PARTIALLY GLAZED/SOLID , FULL/LOW HEIGHT/ PARTITIONS , DOORS &amp; ACCESSORIES. THE RATE INCLUDING DOORS ALONG WITH ALL ACCESSORIES &amp; HARDWARES ETC.</b>					
2.1	<p><b>FULL/HALF HEIGHT SOLID PARTITION</b></p> <p>Full ht. Double skin solid partition :- providing and fixing double skin solid partition , the framing shall made out of aluminium hollow section of 2"x1" size 1.2 mm thick of final / indal as internal frame structure placed horizontally &amp; vertically at max distance of 2'-0" x 2'-0" centre to centre. Fixing 8 mm thick commercial ply (mr grade) on both sides with 1.0mm thick laminate on top of approved shade with groove pattern as per instructions of architect. The rate shall include the cost of providing skirting of 100mm wide lined with 1mm thk laminate and providing &amp; fixing a border at top of 100mm wide lined with 1mm thk laminate complete. Laminate should be considered up to two or three color combination. The edge beadings with steam beach wood should be finished with melamine polish if required, frame work above false ceiling done shall not be measured but contractor may factor it while quoting there rates as measurement up to false ceiling lvl.. .this rate includes p/f in position 35 mm t at 230mm centres, additional support for ac grill shall be fixed as per instruction and ac plan/section/layout. *screw fixing is done mechanically with screw driver of drilling machine with suitable attachment. The board are to be joint and finished so as to have a flush look, which includes filling and finishing the tapered and square edges of the board with jointing compound, paper tape. Note:- for light fittings, grills diffusers and cut-outs, speakers , fire detect</p>	45.00	SMT		

<b>BILL OF QUANTITIES – CIVIL AND INTERIOR FURNISHING WORKS</b>					
<b>Sr.</b>	<b>Particulars</b>	<b>Qty.</b>	<b>Unit</b>	<b>Rate (Rs.)</b>	<b>Amount (Rs.)</b>
	Framework shall be rigidly secured to floor, bottom of slab & existing walls at 2'-0" c/c with fasteners.				
	The Joint B/ween False ceiling and partition shall be filled with silicon sealant (white Transparent colour)				
	Note :- For the purpose of payment partition shall be measured excluding the area of door/door frames up to false ceiling height. The rate including cutting of existing false ceiling for supporting of the frame and refixing of false ceiling in original position, if any.				
<b>2.2</b>	<b>FULL HEIGHT PARTLY GLAZED PARTITION</b>	<b>45.00</b>	<b>SMT</b>		
	Same as the above Solid ht. partition , but providing 8mm thick Modi/saint Gobin float glass above 1'-0" / 3'-0" & up to 7'-0" fixed with steam beech wood beading of finished size 1 1/2" X 1" all along the edge. All edge-to-edge glass joint to be machine cut and polished and sealed with silicon sealant. joint shall be located strictly as shown in the drawing. All exposed woodwork to be melamine polished. Item includes frosted/striped/designer glass film of 3M make/ Avery Dennison or equivalent ( basic rate of Film Rs. 50/ Sq.ft. ) on existing glass as per manufacturer's specifications. All as per the design and instruction Of Architect/Bank 's Engineer.				
<b>2.3</b>	<b>LOW. HEIGHT SEMI GLAZED PARTITION .</b>	<b>50.00</b>	<b>SMT</b>		
	Same as above but of Low height as per design including 10mm Toughened glass with machine edges polished to be used. All other specs are same as of above, Edges of the partition to be covered with 3" X 1.5" Steam beech wood duly melamine polished moulding. Item includes frosted/striped/designer glass film of 3M/ Avery Dennison or equivalent ( basic rate of Film Rs. 50/ Sq.ft. ) on existing glass as per manufacturer's specifications. All as per the design and instruction of Architect/Bank 's Engineer.				
<b>2.4</b>	<b>SINGLE SKIN PARTITION</b>	<b>10.00</b>	<b>SMT</b>		
	As of the above but Providing and fixing single skin partition <b>above false ceiling</b> (where false ceiling is provided only on one side) for a height of up to 600mm or near about soffit of roof using aluminium frame as specified above along with 8 mm thick SINGLE skin fire rated board consisting of aluminium frame works 50mm x 50mm size,1.2mm thick of JINDAL / INDAL as internal frame structure placed horizontally & Vertically at max distance of 2'-0" x 2'-0" centre to centre in position at reqd.spacing but not exceeding 600 mm c/c in either direction and covered. Partition framework to be secured to roof, structural support and nearest structural member using galvanized metal screws and wooden / PVC rowel plugs and all joint to be covered by paper tape finished with two coats of putty, one coat of primer & two coats of plastic emulsion paint as per Architect/Bank's Engineer directions.				
<b>2.5</b>	<b>PARTITION WITH ACCOUSTICAL GLASS WOOL</b>	<b>20.00</b>	<b>SMT</b>		
	Providing and fixing partition framing shall consist of 2" x 1" x 1.2mm thk aluminium tubular frame at 600mm c/c.bothways horizontally and vertically. This framing would be covered by 8 mm thk. Calcium silicate board on both the sides with glass wool insulation (density 25 kg/cum-min) in between the partition and finished with approved 1.0 mm thk approved laminate on both sides in plumb/level with the hairline grooves, wooden moulding,lipping etc. Finished with melamine finish on wooden mouldings. This includes p/f in position 35 mm thk solid core flush door (with 6 mm thk vision glass window),finished with 1.0 mm thk. Approved laminate of approved pattern from both sides and inclusive of heavy duty brass hinges of 100 x 25mm & approved make door closer along with approved make cylindrical lock and t.w.biding wherever required. All the exposed wooden /unfinished surfaces to be painted/polished with approved shade and matching laminate as specified complete the same as indicated in drg & directed by architect. Note: height of partition up to soffit of false ceiling shall be considered for payment.				
	Framework shall be rigidly secured to floor, bottom of slab & existing walls at 2'-0" c/c with fasteners.				
	The Joints Between False Ceiling and partition shall be filled with silicon sealant (white colour)				
	Note :- For the purpose of payment partition shall be measured including the area of door/door frames up to false ceiling height. The rates including cutting of existing false ceiling for supporting of the frame and refixing of false ceiling in original position				

<b>BILL OF QUANTITIES – CIVIL AND INTERIOR FURNISHING WORKS</b>					
<b>Sr.</b>	<b>Particulars</b>	<b>Qty.</b>	<b>Unit</b>	<b>Rate (Rs.)</b>	<b>Amount (Rs.)</b>
2.5	<b>LOW / FULL HEIGHT PARTITION WITH CALCIUM SILICATE –( 1 mm thick Laminate Finish With 8mm thk Glass window)</b>				
a)	(Both side laminate/ partly 8mm thk glazed partition), but partition shall 1.2mm thick aluminium tubular frame at 2' 0"x 2'0" c/c both ways along with 8 mm thk. Calcium silicate board on both side and plain glass fixed between 3'-0" & 4'-6" in height along with 3" x 1" c.p.t. Wood beading on the top of partition finish with matching French polish etc. All the exposed surfaces of the partition shall be finish with approved shade /make 1.00mm thick laminate etc. Complete as per detail drawing and instructions of the architect / bank's engineer.	30.00	SMT		
2.6	<b>TOUGHNED GLASS DOOR &amp;PARTITION</b>				
i	Fixed partition :providing and fixing full height glazed partition made out of 12mm thick 100% toughened approved make glass as per drawing. The work includes machine edge polish with approved make (ozone/dorma xl-c/ enox/ arches) patch fitting with required hardware complete.( all hardware & patch fittings to be finished with s.s brushed finish).	13.00	SMT		
ii	<b>TOUGHNED GLASS DOOR (6'-0" x 7'-0")-2 Nos</b> Providing and fixing 12 mm thick frameless machine polished edge toughened glass door shutter of approved brand and manufacture, including providing and fixing with approved brand top & bottom pivot & double acting hydraulic floor spring type fixing arrangement And making necessary holes etc. For fixing required door fittings, all complete as per direction of architect/engineer-in-charge .the rate including door pull/ push handle of length 24", thickness 25 mm with bottom lock and stopper of approved brand etc. Complete as per detail drawing and instructions of the architect / bank's engineer.	7.90	sqm		
iii	<b>Aluminium Composite Panelling Works</b> Providing and fixing of Aluminium composite panel as per the drawing/specifications for the exterior finishing job. ACP of approved make (Alstrong, Aludecor, Alto Bond or approved equivalent) of over all thickness is 4 mm with aluminium skin of 0.25 mm on both sided, centre LDPE core material of thickness 4 mm. [FR Grade with Intricate design Jhali (lattice) by CNC routers/laser cutter) The complete material shall be confirming to ASTM standards for its various mechanical and physical properties.  The panel shall be cut into match the grid size in required length and width as per the site condition, tampered & formed using router machine/curved using standard rolling machine, without leaving heavy marks on the sheet, so as to form a tray. The panel shall be fixed on pre-fabricated frame work using 50 x 25 x 1 mm thick aluminium extruded sections of Hindalco/Jindal make, joint at Horizontal & Vertical with Standard cleat angles and fasteners of SS screws, Hilty / Fisher anchor bolt. The gap formed in between the panel shall be sealed with silicon sealant of approved make or equivalent after fixing the required masking tape and all other accessories as per the manufacture's specifications. The sheet fixing and applying of sealent shall be in line and level to the building line. The extruded pre fabricated frame work shall be fixed to the wall/floor beam with M.S brackets and screws. The necessary projection as per the design shall be made with M.S frame work using 35x35x6 mm M.S angles fixed at maximum 1.5 m centre to centre fixed to the super structure.  The panel colours will be of approved make/Grade changes in colour, materials shall be made only with prior intimation to the Architect and the Bank authorities.	160.00	sqm		
iv	<b>Structural Glazing Works</b> Supplying and fixing at site structural glazing using electro colour anodized approved shade to minimum 15 microns using Indal 8989 for Mullion and Transom with Indal same for top and bottom horizontal members with Indal 2081 to be used as joining cleats. The entire structural glazing system to be fabricated single glazing using Dowcorning 995 accelerated cure for structural sealant and 789 for weather seal. Weather gaskets shall be of EPDM of approved quality 4x6mm Norton spacer tapes of approved quality, Including cost and conveyance of all materials to site, labour charges for erection, lead, lift, transportation, handling charges, hire charges for scaffolding etc. Complete including fixing in position after cutting from standard sizes of 6mm reflective glasses structured with the design/pattern colour as per manufacture's specifications				

**BILL OF QUANTITIES – CIVIL AND INTERIOR FURNISHING WORKS**

Sr.	Particulars	Qty.	Unit	Rate (Rs.)	Amount (Rs.)
	<p>a) Providing and supplying Spandrel Glass Panels (structural glazing) comprising of 6mm thick heat strengthened monolithic float glass of approved colour and shade so as to match the colour and shade of the building external paint, all complete for the required performances as specified, as per the Architectural drawings, as per the approved shop drawings, as specified and as directed by Engineer-in-charge/Consulting Architect. For payment, only the actual area of glass on face #1 of the glass panels (but excluding the area of grooves and weather silicone sealant) provided and fixed in position, shall be measured in sqm. (Payment for fixing of Spandrel Glas Panels in the curtain glazing is included in cost of relevant Item). (i) Coloured tinted float glass 6mm thick substrate with reflective soft coating on face #2, having properties as visible Light transmittance(VLT) of 20 to 35%, Light reflection internal 10 to 15%, light reflection external 10 to 20%, shading coefficient(0.25-0.28) and U value of 3.0 to 3.3 W/m2 K etc. The properties of performance glass shall be decided by Consulting Architect &amp; Engineer-in-charge.</p>	200.00	sqm		
	<p>b) The Structural glazing using electro colour anodized black shade to minimum 15 micron using Indal/approved 8989 For Mullion &amp; Transom with same for top &amp; bottom horizontal members with Indal/approved make 2081 to be used as Joining Cleats. The entire structural glazing system to be fabricated single glazing using Dow corning 995 accelerated cure for structural sealant &amp; 789 for weather seal, weather gasket shall be of EPDM od approved quality, 4 x 6 mm Norton spacers tapes of approved quality, reducing cost &amp; conveyance of all materials to site, labour charges for erection, lead, lift, transportation, handling charges, hire charges for scaffolding etc. Complete including fixing in position of the cutting from standard sizes of 6mm THK reflective structural glasses with the design/pattern, colour tinted as per manufacturer's specification.</p>				
3	<p><b>Double beds (size - 6'-0" x 6'- 3" x 1'-6"ht) with 5" thk Approved make / Brand mattress/headboard with 12mm thk bwr ply backing &amp; Fabric / Foam leather as per pattern.</b></p>	0.00	NOS		
	<p>Double bed with headboard made of 12mm thk ply backing ,t.w. Edging melamine polish with 12mm thick foam padding and approved fabric/ foam leather finish all around the bed facia &amp; 25 mm thick foam padding for headboard with approved fabric/ foam leather. 32mm x 32 mm ,18 gauge square ms frame work bed structure finished with approved colour powder coating and 18mm thick base ply as per detail &amp; specifications attached. As per approved design of architect. ( prototype of bed sample to be provided for approval)</p>				
4	<p><b>Single bed for students in hostel room (size - 3'-0" x 6'-3" x 1'-6"ht) with 4" thick Approved make/ Brand mattress/headboard with 12 mm thk bwr ply backing</b></p>	101.00	NOS		
	<p>Single bed with head board made of 12mm thk ply backing ,t.w. Edging melamine polish with 1 mm thick approved laminate finish all around the bed facia &amp; headboard with 32mm x 32 mm ,18 gauge square ms frame bed structure finished with approved colour powder coating and 18mm thk base ply as per detail &amp; specifications attached. As per approved design of architect. (prototype of bed sample to be provided for approval).</p>				
5	<p><b>STORAGE</b></p>				
5.1	<p><b>LOW HT STORAGE WITH LAMINATE FINISH</b></p>				
	<p>P/F in position 450mm deep storage low height cabinets having sides partitions shelves &amp; shutters, fabricated out of 19mm comm.ply &amp; 9 mm th.comm Plywood back, with all exposed surfaces to be finished with 1mm thk. Laminate as per approved shade and inside of shutters/internal as per approved. Shade to be finished with 0.8 mm thk laminate in all internal surfaces of &amp; P/F Laminate 1mm thk. skirting(100mm) as per appvd.Sample i/c 31x31mm rounded steam beech wood moulding &amp; 6x19 mm steam beech wood edging on edges of comm. board as/arch.drg.complete with with P/F shelves,shutter,drawers etc.i/c P/F necessary hardware telescopic channels of approved make for drawers and shutter shall be fixed with Hydraulic concealed hinges as/appvd.sample, 6"/8" Long SS handles(as /appvd sample) in all drawers &amp; shutters ,locking arrangement, 75mm S.S tower bolts,Hettich/godrej locks in all shutters, magnet catcher. All the surface shall be finished with Laminate , no painting is allowed etc.</p>	50.00	SMT		

<b>BILL OF QUANTITIES – CIVIL AND INTERIOR FURNISHING WORKS</b>					
<b>Sr.</b>	<b>Particulars</b>	<b>Qty.</b>	<b>Unit</b>	<b>Rate (Rs.)</b>	<b>Amount (Rs.)</b>
5.2	<b>FULL HT STORAGE WITH LAMINATE FINISH</b>	75.00	SMT		
	P/F in position 450mm deep storage full height cabinets having sides partitions shelves & shutters, fabricated out of 19mm comm.ply & 9 mm th.comm Plywood back, with all exposed surfaces to be finished with 1mm thk. Laminate as per approved shade and inside of shutters/internal as per approved. Shade to be finished with 0.8 mm thk laminate in all internal surfaces of & P/F Laminate 1mm thk. skirting(100mm) as per appvd.Sample i/c 31x31mm rounded steam beech wood moulding & 6x19 mm steam beech wood edging on edges of comm. board as/arch.drg.complete with with P/F shelves,shutter,drawers etc.i/c P/F necessary hardware telescopic channels of approved make for drawers and shutter shall be fixed with Hydraulic concealed hinges as/appvd.sample, 6"8" Long SS handles(as /appvd sample) in all drawers & shutters ,locking arrangement, 75mm S.S tower bolts,Hettich/godrej locks in all shutters, magnet catcher. All the surface shall be finished with Laminate , no painting is allowed etc.				
5.3	<b>WARDROBE</b>	100.00	SMT		
	Providing & fixing 550mm deep approx. 1800mm ht.wardrobe unit as per drg. And details. The storage unit should be made out of 18mm thk. marine ply for top, sides and base, 6mm thk. Marine ply backing, 25mm thk block board (marine) shutters with auto closing hinges and t.w.lipping matching with approved laminate on all the edges. All external surfaces to be finished in 1mm thk laminate (suede finish) of approved make division of shutters (approx.450 mm) shall be made equally according to the length of the storage all internal surfaces to be finished with 0.8 mm thk laminate ,the exposed surfaces to be finished with the matching melamine polish and complete. Rates shall be inclusive of all necessary approved fittings like auto closing hinges, locks, concealed handles, telescopic drawer channels, tower bolts and any miscellaneous hardware items as per engineer-in charge / architect's instructions.				
5.4	<b>PANTRY FRAME CUPBOARDS</b>	25.00	SMT		
	Providing and fixing pantry platform shutters with 19 mm thk. Marine ply both side finished with 1.0 mm thk. Finished laminate. Shutters to be fixed with 2" x 1" t. W. Frame ( French polish of matching shade ) with 2 no. 3" x 3/4" s.s. Hinges, brush finished s. S. Pull handles, magnetic ball catches , 3" tower bolts etc. Complete as per architect's instructions.				
5.5	<b>LUGGAGE RACK</b>	2.50	SMT		
	P/f in position luggage rack is made out of 19 mm thk commercial ply for top,bottom,sides, back. All exposed surfaces to be finished with combination of 1mm thk laminate & all internal surfaces of the ply finished with 0.8 mm thk laminate. Item to be completed as per drg & site directions. Item to include all types of hardwires, screws, ss handles, tower bolts, ball catches, wooden lipping,bedding,s.s. 3mm x 6mm s.s. Inlay patti on top @ 1" c/c & t.w. Melamine polish moulding etc.				
6	<b>TYPICAL TV UNIT PANELLING APPROX (1.30 X 1.30)</b>	4.00	NOS		
	Providing and fixing tv unit panelling with 3 " depth on wall with 1 mm thk laminate finish panelling to concealed switch boards, cables and conduits made out of 2" x 1" c.p.teak wooden frame work at every 1.5" c/c (horizontal & vertical) covered with 9mm thick marine ply along with 1.3 meter ht. Or more, cut-out in panelling to recessed the TV size with shutter on top . 4"x3/4" brass hinges, 12 mm thk backing on wall, magnetic ball catch etc, complete as per design & directed by architect.				
7	<b>S/I approved make of 30 - 32 mm thk WPC TOILET DOOR WITH FRAME )</b> thickness Approx. 100mmX50mm in a position including heavy duty S.S. Hinges 3 nos and 2 nos S.S. Tower bolts and 1 no approved make S.S. Lever handle without lock for washroom door . (Prototype of door sample to be provided for approval)				
	<b>(0.75 mX 2.1m)</b>	61.00	Nos		
	<b>(0.90m X 2.1m)</b>	2.00	Nos		
	<b>(1.00m X 2.1m)</b>	1.00	Nos		

**BILL OF QUANTITIES – CIVIL AND INTERIOR FURNISHING WORKS**

Sr.	Particulars	Qty.	Unit	Rate (Rs.)	Amount (Rs.)
9	<b>Approved make WPC SHAFT DOOR</b> Approx. 1.2m x1.2m, 30-32 mm thick shutter , 2 shutter with door frame thickness approx. 75mmx50 thk in a position including heavy duty s.s. Hinges 4 nos ,with 1 no s.s. Tower bolt with shaft locking arrangement, colour shall be matching to the wall tile colour as directed. ( prototype of frame sample to be provided for approval).	40.00	SQ.MT		
10	<b>MARINE FLUSH DOOR</b>				
	Providing & fixing of 1-1/2" th. Solid core marine flush door with necessary lipping etc. Complete finished with 1.0 mm thk. Finish laminate from both sides fixed to ms frame / wall / partition panelling with 3 no. 5" x 1-1/4" heavy duty s.s. Hinges,s.s.tower bolt, door closure -1 no each door shutter, 3 coats of enamel paint / polish at side thickness of shutter & provision of glazed panel etc. Complete. (location as indicated)				
a)	Size : i) 3' 0" x 7' 0" (hostel & guest rooms) with Heavy duty Mortise lock and lever handle with S.S. Finish or Powder Coated 3 NO. 5" X 1-1/4" Heavy Duty S.S. HINGES,S.S.TOWER BOLT,as approved fixed to the Existing Metal/ Wooden door frame. As Directed by Architect/ Bank's Engineer.	47.00	No		
b)	Size : i) 5' 0" x 7' 0" (class rooms & training rooms) - DOUBLE DOOR. With approved Dead Lock with 450mm S.S. PULL HANDLE (2Nos Each door, back to back) with vision panel, 2 nos. approved door closers for each shutter, as approved with concealed wooden door frame in the panelling. As Directed by Architect/ Bank's Engineer.	6.00	No		
c)	Size : i) 4' 0" x 7' 0" (other areas)With approved Dead Lock with 450mm S.S. PULL HANDLE (2Nos Each door, back to back) with vision panel, 1 nos. approved door closers for shutter, as approved with concealed wooden door frame in the panelling. As Directed by Architect/ Bank's Engineer.	5.00	No		
d)	Size : i) 6' 0" x 7' 0" (cafeteria entrance) - DOUBLE DOOR. With approved Dead Lock with 450mm S.S. PULL HANDLE (2Nos Each door, back to back) with vision panel, 2 nos. approved floor spring for each shutter, as approved with concealed wooden door frame in the panelling. As Directed by Architect/ Bank's Engineer.	1.00	No		
11	Supplying and fixing 16 gauge aluminium anodised coated ( minimum 50 micron powder coating) ventilator frame of size 50mmx25mm with adjustable aluminium 100 mm size louvers and provided with 100mm wide and 5mm thick wired / pinned glass. External face of ventilator shall be covered with gi rat mesh fixed in 25mmx12 mm aluminium anodised coated ( minimum 50 micron powder coating) frame , and to be fixed on the wall. The rate including costs of all materials including non corrosive fasteners, labour charges, scaffolding, cleaning etc. Complete ( toilet windows).	0.00	SMT		
<b>D</b>	<b>TABLES</b>				
1	<b>DINING TABLE LAMINATE FINISH (AS PER DESIGN SCHEME)</b>				
	Providing & making new dining table with 19mm thk mr ply covered with 1.5mm thk approved laminate of approved make & colour , the edge of the table to be increased by additional 3" wide band & 12 mm thk ply ( total thickness visibly 30 mm at table edge ) with 6 mm thk& 30 mm wide wooden edge lipping putty on all sides with matching French polish or approved good finished paint . The top to be fixed on brush steel vertical frame & floor base plate with necessary hardware fittings. As per design & directed by architect.				
a)	<b>STAFF DINING (1.20 X 0.90 X 0.75HT)</b>	15.00	No		
b)	<b>EXECUTIVE DINING (0.90 X 0.90 X 0.75HT)</b>	2.00	No		

**BILL OF QUANTITIES – CIVIL AND INTERIOR FURNISHING WORKS**

Sr.	Particulars	Qty.	Unit	Rate (Rs.)	Amount (Rs.)
2	<b>MEETING ROOM TABLE (2.1 X 1.20 X 0.75HT)</b>				
	Providing and fixing as per design with the table top 35 mm thick ply with laminate finished and 35 mm x 35 mm thk wooden edge moulding finished with silk melamine polish. The top shall be 1.5 mm thk approved laminate (in colour pattern joints). The legs (6 nos) made up of 75 x 75 mm square m.s. Frame with 9 mm thk mr grade ply to paste & finish with 1 mm thk approved laminate (in two colours) the foot rest to be made out of 19 mm thk mr grade ply finished with 1 mm thk approved laminate. The modesty panel made out of 18 mm thk mr grade ply finished with 1 mm thk laminate on both the sides with laminated edge beading. Etc complete as per detail drawing & instructions of the architect / engineer - in - charge.	1.00	No		
3	<b>CONFERENCE TABLE (4.20 X 1.20 X 0.75HT)</b>				
	Providing and fixing as per design with the table top 35 mm thick ply with laminate finished and 35 mm x 35 mm thk wooden edge moulding finished with silk melamine polish. The top shall be 1.5 mm thk approved laminate (in colour pattern joints). The legs (10 nos) made up of 75 x 75 mm square m.s. Frame with 9 mm thk mr grade ply to paste & finish with 1 mm thk approved laminate (in two colours) the foot rest to be made out of 19 mm thk mr grade ply finished with 1 mm thk approved laminate. The modesty panel made out of 18 mm thk mr grade ply finished with 1 mm thk laminate on both the sides with laminated edge beading. Etc complete as per detail drawing & instructions of the architect / engineer - in - charge.	1.00	No		
4	<b>PRINCIPAL TABLE (1.8 X 0.90 X 0.75HT) R- (1.10 X 0.45 X 0.70HT)</b>				
	Providing & fixing work table with side runner made out of 1mm thk approved laminate top with 25mm thick mr ply frame work for table. Side table, sides, top front apron, shutters, unit sides, 12mm thick mr ply for drawer sides, key board sides, sliding shutters, 6mm thick mr ply for back, drawer unit back, drawer bottom etc. With 3" x 6mm, 1" x 1", 1 1/2" x 1 1/2" c.p.t. Wood bedding & moulding etc with silk melamine polish. Complete. The table front shall have 12mm thick mr ply panels with 4" x 12mm thick border along with one drawer unit with one drawer for pencil tray, 3 nos. Of equal drawers, key board drawer & side table shall have 3" deep 2 nos. Drawer at top & sliding shutter below the drawers etc. Complete. All the exposed wooden /unfinished surfaces to be finished with approved shade and matching with approved laminate as specified & inside surfaces finish with 0.8mm thk approved laminate along with approved make / design hardware such as twin telescopic sliding channels, s.s. Handles, s.s. Hinges, 12mm thk mr plywood of 2'-0" x 1'-6" x 9" in height slope type foot rest finish with woollen carpet, powder coated cpu trolley, suspended type brushed steel flush wire manager, complete as per detail drawing & instructions of the architect / engineer - in - charge.	0.00	No		
5	<b>VICE PRINCIPAL / IBLA/ FACULTY TABLE (1.50 X 0.75 X 0.75HT) R- (0.90 X 0.45 X 0.75HT)</b>				
	Providing & fixing vp table with side runner made out of 1mm thk approved laminate top with 25mm thick mr ply frame work for table table top, side table, sides, top front apron, shutters, unit sides, 12mm thick mr ply for drawer sides, key board sides, sliding shutters, foot rest, 6mm thick mr ply for back, drawer unit back, drawer bottom etc. With 3" x 6mm, 1" x 1", 1 1/2" x 1 1/2" c.p.t. Wood bedding & moulding etc with silk melamine polish. Complete. The table front shall have 12mm thick mr ply panels with 4" x 12mm thick border along with one drawer unit with one drawer for pencil tray, 3 nos. Of equal drawers, key board drawer & side table shall have 3" deep 2 nos. Drawer at top & sliding shutter below the drawers etc. Complete. All the exposed wooden /unfinished surfaces to be finished with approved shade and matching with approved laminate as specified & inside surfaces finish with 0.8mm thk approved laminate along with approved make / design hardware such as twin telescopic sliding channels, design handles, brass hinges, 12mm thk mr plywood of 2'-0" x 1'-6" x 9" in height slope type foot rest finish with woollen / pvc carpet, powder coated cpu trolley, suspended type brushed steel flush wire manager, complete as per detail drawing & instructions of the architect / engineer - in - charge.	1.00	No		

**BILL OF QUANTITIES – CIVIL AND INTERIOR FURNISHING WORKS**

Sr.	Particulars	Qty.	Unit	Rate (Rs.)	Amount (Rs.)
6	<p><b>FACULTY TABLE (1.50 X 0.60 X 0.75HT) R- (0.90 X 0.45 X 0.75HT)</b></p> <p>Providing &amp; fixing faculty table with side runner made out of 1mm thk approved laminate top with 18mm thick mr ply frame work for table top, side table, sides, top front apron, shutters, unit sides, 12mm thick mr ply for drawer sides, key board sides, sliding shutters, foot rest, 6mm thick mr ply for back, drawer unit back, drawer bottom etc. With 3" x 6mm, 1" x 1", 1 1/2" x 1 1/2" c.p.t. Wood bedding &amp; moulding etc. Complete. The table front shall have 12mm thick mr ply panels with 4" x 12mm thick border along with one drawer unit with one drawer for pencil tray, 3 nos. Of equal drawers, key board drawer &amp; side table shall have 3" deep 2 nos. Drawer at top &amp; sliding shutter below the drawers etc. Complete. All the exposed wooden /unfinished surfaces to be finished with approved shade and matching with approved laminate as specified &amp; inside surfaces finish with 0.8mm thk approved laminate along with approved make / design hardware such as twin telescopic sliding channels, design handles, brass hinges, 12mm thk mr plywood of 2'-0" x 1'-6" x 9" in height slope type foot rest finish with woollen /pvc carpet, powder coated cpu trolley, suspended type brushed steel flush wire manager, complete as per detail drawing &amp; instructions of the architect / engineer - in - charge.</p>	11.00	No		
7	<p><b>LIBRARIAN TABLE (1.80 X 0.60 X 0.75HT)</b></p> <p>Providing &amp; fixing librarian table made out of 1mm thk approved laminate top with 18mm thick mr ply frame work for table, sides, top front apron, shutters, unit sides, 12mm thick mr ply for drawer sides, key board sides, sliding shutters, foot rest, 6mm thick mr ply for back, drawer unit back, drawer bottom etc. With 3" x 6mm, 1" x 1", 1 1/2" x 1 1/2" c.p.t. Wood bedding &amp; moulding etc. Complete. The table front shall have 12mm thick mr ply panels with 4" x 12mm thick border along with one drawer unit with one drawer for pencil tray, 3 nos. Of equal drawers, key board drawer &amp; side table shall have 3" deep 2 nos. Drawer at top &amp; sliding shutter below the drawers etc. Complete. All the exposed wooden /unfinished surfaces to be finished with approved shade and matching with approved laminate as specified &amp; inside surfaces finish with 0.8mm thk approved laminate along with approved make / design hardware such as twin telescopic sliding channels, design handles, brass hinges, 12mm thk mr plywood of 2'-0" x 1'-6" x 9" in height slope type foot rest finish with woollen /pvc carpet, powder coated cpu trolley, suspended type brushed steel flush wire manager, complete as per detail drawing &amp; instructions of the architect / engineer - in - charge.</p>	1.00	No		
8	<p><b>HOSTEL STUDY TABLE WITHOUT SIDE RUNNER (0.90 X 0.60 X 0.75HT)</b></p> <p>Providing &amp; fixing officer table with side runner made out of 1mm thk approved laminate top with 18mm thick mr ply frame work for table, side table, sides, top front apron, shutters, unit sides, 12mm thick mr ply for drawer sides, key board sides, sliding shutters, foot rest, 6mm thick mr ply for back, drawer unit back, drawer bottom etc. With 3" x 6mm, 1" x 1", 1 1/2" x 1 1/2" c.p.t. Wood bedding &amp; moulding etc. Complete. The table front shall have 12mm thick marine ply panels with 4" x 12mm thick border along with one drawer unit with one drawer for pencil tray, 3 nos. Of equal drawers, key board drawer &amp; side table shall have 3" deep 2 nos. Drawer at top &amp; sliding shutter below the drawers etc. Complete. All the exposed wooden /unfinished surfaces to be finished with approved shade and matching with approved laminate as specified &amp; inside surfaces finish with 0.8mm thk approved laminate along with approved make / design hardware such as twin telescopic sliding channels, design handles, brass hinges, 12mm thk mr plywood of 2'-0" x 1'-6" x 9" in height slope type foot rest finish with pvc/ laminate, powder coated cpu trolley, suspended type brushed steel flush wire manager, complete as per detail drawing &amp; instructions of the architect / engineer - in - charge.</p>	95.00	No		
9	<p><b>LIBRARY CLUSTER TYPE TABLE (0.90 X 0.45 X 0.75HT)</b></p> <p>Providing &amp; fixing librarian table with side runner made out of 1mm thk approved laminate top with 18mm thick mr ply frame work for table, side table, sides, top front apron, shutters, unit sides, 12mm thick mr ply for drawer sides, key board sides, sliding shutters, foot rest, 6mm thick mr ply for back, drawer unit back, drawer bottom etc. With 3" x 6mm, 1" x 1", 1 1/2" x 1 1/2" c.p.t. Wood bedding &amp; moulding etc. Complete. The table front shall have 12mm thick marine ply panels with 4" x 12mm thick border along with one drawer unit with one drawer for pencil tray, 3 nos. Of equal drawers, key board drawer &amp; side table shall have 3" deep 2 nos. Drawer at top &amp; sliding shutter below the drawers etc. Complete. All the exposed wooden /unfinished surfaces to be finished with approved shade and matching with approved laminate as specified &amp; inside surfaces finish with 0.8mm thk approved laminate along with approved make / design hardware such as twin telescopic sliding channels, design handles, brass hinges, 12mm thk mr plywood of 2'-0" x 1'-6" x 9" in height slope type foot rest finish with laminate, powder coated cpu trolley, suspended type brushed steel flush wire manager, complete as per detail drawing &amp; instructions of the architect / engineer - in - charge.</p>	0.00	No		

**BILL OF QUANTITIES – CIVIL AND INTERIOR FURNISHING WORKS**

Sr.	Particulars	Qty.	Unit	Rate (Rs.)	Amount (Rs.)
10	<b>PRINTER / UTILITY TABLE LIBRARY (1.00 X 0.60 X 0.75HT)</b>	0.00	No		
	Providing and fixing printer /utility table with top of size 3'-4" x 2'-0" x 1'-6" 18mm thk commercial ply finished with 1 mm thk laminate on top side, front rear & all exposed surfaces and front rear and all exposed surfaces including exposed internal surface front and exposed leg & cpu space to be finished with 1mm thk. Laminate complete 3 set of drawers, key board drawer, shelves & shutter as per arch.drg. Complete with necessary hardware, telescopic sliding channels, of s.s hettich multi purpose efficient locks, hettich handles (150mm) & magnet catcher, sbw moulding 31 x 31 mm & sbw edging (6mm x 19mm) & painting all other exposed internal surfaces with 2 or 3 coats of synthetic enamel paint & all wooden surface with melamine polish finish inclusive of p/f stainless steel cable manager and making good the surface. The cost include providing & fixing of hardwood wooden footrest (3" x 1-1/2"), sliding keyboard drawer, cable manager, cpu trolley (9" x 18") all ebco make. Border/skirting as per the bank/architect direction has to be provided as per				
11	<b>CLASSROOM DESK</b>				
	Providing and fixing classroom desk with various sizes as indicated below & as shown in drawing. The workstation table top of 18mm thk mr commercial ply finished with 1 mm thk laminate (in two colours) on top side, front, rear & all exposed surfaces including exposed internal surface front and exposed leg & cpu space to be finished with 1mm thk. Laminate with hard pvc key board drawer as per arch.drg. All wooden surface with melamine polish finish inclusive of p/f stainless steel cable manager .the top to have 6" front ledge to install electrical gadgets (switch plates) & making good the surface. The cost include providing & fixing of wooden footrest (3" x 1-1/2"). All approved make. Border/skirting as per the bank's engineer / architect direction .				
a)	(Approx sizes 1.06 X 0.45 X 0.75/0.90HT)	12.00	No		
b)	(Approx sizes 1.75 X 0.45 X 0.75/ 0.90HT)	30.00	No		
c)	(Approx sizes 2.10 X 0.45 X 0.75/0.90HT)	4.00	No		
12	<b>COMPUTER TABLE LIBRARY (0.75 X 0.60 X 0.75HT)</b>	4.00	No		
	Providing and fixing computer desk as per design and the top to be made out of 18mm thick mr ply wood and all exposed surface to be fixed with approved 1mm thk laminate. And & inside surfaces finish with 1 mm thk approved laminate, (cost of the table to include drawer,cpu ,key board drawer , foot rest, wire manager and shutter with all brushed steel hardware fittings and fixtures) as per design and as directed by the architect/ bank engineer.				
13	<b>RECEPTION DESK (2.10 X 0.75 X 0.75HT)</b>				
	Providing & fixing reception table with work top with 18mm thick mr ply with approved brand 6 mm thk corian materia including thickness of, top front apron, shutters, unit sides, 12mm thick mr ply for drawer sides, key board sides, sliding shutters, foot rest, drawer bottom etc. With 3" x 6mm, 1" x 1", 1 1/2" x 1 1/2" c.p.t. Wood bidding & moulding etc. Complete. Cost of the table to include with 3 drawer and single shutter attached storage unit with all hardware fittings & fixtures as per drgs & as directed by architect. All the exposed wooden /unfinished surfaces to be finished with approved shade and matching with approved 1 mm thk laminate as specified & inside surfaces finish with 0.8mm thk approved laminate. The table to have s.s. Pop-up wire managers as per the instructions & design of the architect.	1.00	No		
14	<b>CONSOLE UNIT WITH STORAGE BELOW</b>				
	Providing and fixing at location console unit of size 1500x 450x 750mm ht as per design and the top to be made out of 19mm thick mr ply wood with approved brand 6 mm thk corian material including thickness of top and all exposed surface to be fixed with approved 1mm thk laminate & inside surfaces finish with 0.8mm thk approved laminate, (cost of the table to include two shutters with all brush steel hardware fittings such as handles ,lock ,hinges and fixtures etc) as per design and as directed by the architect/ bank engineer.	1.00	NOS		

**BILL OF QUANTITIES – CIVIL AND INTERIOR FURNISHING WORKS**

Sr.	Particulars	Qty.	Unit	Rate (Rs.)	Amount (Rs.)
15	<b>Corien top Laying</b> : Providing and Fising of 6mm Corian solid surface tops over the existing table top installed over 19mm boiling water-resistant (BWR) plywood. Approved Brand HIMACS (LX Hausys), Staron (Samsung), and Tristone.,LG) .The rate including jointing ,polishing,edge polishing etc . NOTE :Whereever shall install , uniform cost of Lamination will be deducted i.s Rs.700/per Sqm	50.00	sqm		
<b>E</b>	<b>SOFA / SIDE TABLES &amp; CHAIRS</b>				
	Providing and making sofa of overall sizes as mentioned in the drawing; with back and armrests. The sofa will consist of well-seasoned c.p teakwood frame of size 2"x1.5", seat base provided with flat (zig-zag) spring of "k1" make and covered with cloth from bottom as well as top and back. The armrest will be made of well-seasoned 1st quality c.p teak wood frame. The seat and back frame faced with 100mm thick approved 40-50 high density foam internally of sleep-well/mm/ king brand and 4mm thick ply from outer side and covered with approved upholstery (approximately rs650/rmt). All exposed wooden surface shall be polished in 3 coats of melamine finish. Rates shall be inclusive of all accessories and scotch guard treatment for upholstery.				
1	<b>2-SEATER SOFA</b>	12.00	No		
	Two seater sofa size 4'-0" x 2'-6" with fabric finish (rs. 650/- mtr)as per details & design given by architect.				
2	<b>3-SEATER SOFA</b>	1.00	No		
	Three seater sofa size 6'-6" x 2'-6" with fabric finish (rs. 650/- mtr)as per details & design given by architect.				
3	<b>1-SEATER SOFA</b>	4.00	No		
	One seater sofa size 2'-6" x 2'-6" with fabric finish (rs. 650/- mtr)as per details & design given by architect.				
4	<b>SOFA SIDE TABLE LAMINATE FINISH</b>	10.00	No		
	Sofa side table of size 20" x 20"x18" in 10 mm thk glass top with beveled edges & laminate finish.as per details & design given by architect.				
5	<b>CENTER TABLE SQUARE/ CIRCULAR SHAPE</b>	12.00	No		
	Size of the table 3'-0" x 1'-6" x 1'-6" ht.in wood finish with 10 mm thk glass top with bevelled edge. As per details & design given by architect.				
6	<b>CHAIR COMPANY NAME - (HOF / GODREJ / CHARM / DURIAN). The rate shall be percentage increase to the basic rate</b> indicated in the description below including all taxes, over head charges and contractor's profit etc. Complete.				
*	Base- 5 Prongs glass filled nylon stand.				
*	Castors- Twin wheel type Nylon castor.				
*	Height adjustment- Imported gas lift mechanism.				
*	Mechanism- Imported synchro tilt mechanism with multi angle locking facility.				
*	Seat and back cushions- Made out of soft moulded polyurethane foam of 48 density.				
*	Handles- cold cure moulded soft polyurethane.				
*	Fabric (BASIC RATE RS.650- RMT)/ foam leather- As approved by the architect/ bank engineer.				
a)	<b>HIGH BACK CHAIR FOR (PRINCIPAL)</b>				
	High back chair/ revolving / gas height adjustment /tilting mechanism / upholstered arms with pu padding / chrome base with twin wheel castors. Upholstery -quilted foam leather. Total high of the chair 47", seat size 17.5" x 22.5" back size 31" x 23" ergonomically designed as pe detail drawing /views attached. (basic rate = rs.7500/no.)	2.00	No		
b)	<b>MEDIUM BACK VISITOR CHAIR FOR PRINCIPAL</b>				
	Medium back chair/ revolving / gas height adjustment /tilting mechanism / wooden arms with pu padding / chrome base with twin wheel castors. Upholstery - approved febric.total hight of the chair 39", seat size 17.5" x 22.5" back size 25" x 23" ergonomically designed. (basic rate = rs.6500/no)	3.00	No		

<b>BILL OF QUANTITIES – CIVIL AND INTERIOR FURNISHING WORKS</b>					
<b>Sr.</b>	<b>Particulars</b>	<b>Qty.</b>	<b>Unit</b>	<b>Rate (Rs.)</b>	<b>Amount (Rs.)</b>
c)	<b>MEDIUM BACK CHAIR (VICE PRINCIPAL / IBLA MEETING &amp; CONFERENCE)</b>				
	Medium back chair/ revolving / gas height adjustment /tilting mechanism / wooden arms with pu padding / chrome base with twin wheel castors. Upholstery - approved febric.total height of the chair 39", seat size 17.5" x 22.5" back size 25" x 23" ergonomically designed. (basic rate = rs.6500/no)	36.00	No		
d)	<b>LOW BACK VISITOR CHAIR (VICE PRINCIPAL / IBLA CABIN)</b>				
	Low back chair / revolving / gas height adjustment /permanent contact mechanism / pp fixed arms / nylon base with twin wheel castors. Upholstery approved fabric 37" ht of the chair, seat size 19" x 19" back size 19"x 17". Ergonomically design. (basic rate = rs.4500/no)	4.00	No		
e)	<b>LOW BACK CHAIR (RECEPTION &amp; FACULTY)</b>				
	Low back chair / revolving / gas height adjustment /permanent contact mechanism / pp fixed arms / nylon base with twin wheel castors. Upholstery approved fabric 37" ht of the chair, seat size 19" x 19" back size 19"x 17". Ergonomically design. (basic rate = rs.4500/no)	12.00	No		
f)	<b>VISITOR CHAIR FOR FACULTY</b>				
	Low back chair / pp fixed arms / fixed metal base. Upholstery quilted foam leather 37" ht of the chair, seat size 19" x 19" back size 19"x 17". Ergonomically design. (basic rate = rs.3500/no)	20.00	No		
g)	<b>HOSTEL ROOM STUDY CHAIR</b>				
	Low back chair / without arms / fixed metal base. Upholstery quilted foam leather 37" ht of the chair, seat size 19" x 19" back size 19"x 17". Ergonomically design. (basic rate = rs.3500/no)	95.00	No		
h)	<b>LIBRARY &amp; CLASSROOM CHAIR</b>				
	Low back chair / with arms / fixed metal base. Upholstery quilted foam leather 37" ht of the chair, seat size 19" x 19" back size 19"x 17". Ergonomically design. (basic rate = rs.3500/no)	219.00	No		
i)	<b>CAFETERIA CHAIRS</b>				
	Portable chair / stacked one atop another / poly-propylene edging 37" ht of the chair, seat size 19" x 19" back size 19"x 17". Ergonomically design. (basic rate = rs.4500/no)	60.00	No		
j)	<b>EXECUTIVE DINING CHAIR</b>				
	Armed chair with cushion in seat & back in hard pvc leather and frame in s.s. brushed steel as per details & design. All furniture made in 304 grade non-magnetic stainless steel. (basic rate = rs.8500/no)	8.00	No		
k)	<b>GUEST ROOM DINING / COFFEE CHAIR</b>				
	Armed chair with cushion in seat & back in hard pvc leather and frame in s.s. brushed steel as per details & design. All furniture made in 304 grade non-magnetic stainless steel. (basic rate = rs.4500/no)	10.00	No		
*	Base - 5 prongs glass filled nylon stand.				
*	Castors - twin wheel type nylon castor.				
*	Height adjustment - imported gas lift mechanism.				
*	Mechanism - imported synchro tilt mechanism with multi angle locking facility.				
*	Back connections rod : 6mm thk powder coated ms solid flat covered with polypropylene.				
*	Seat and back cushions - made out of soft moulded polyurethane foam of 48 density				
*	Handles - cold cure moulded soft polyurethane.				
*	Fabric (basic rate rs.200/- rmt) - as approved by the bank / architect.				
<b>F</b>	<b>MISCELLANEOUS ITEMS</b>				
1	<b>VINYL GLASS FILM</b>				
	Providing and applying privacy film on internal glass partition or window/door glass panels neatly complete as directed by the architect/bank engineer. The film shall be strength enabling it to the safety glazing standards ansi97.1 and cpsc 16cfr. The film shall block 98% of the damaging uv rays anf has abrasion resistant as per astm d 1044 standards (make : garware/lg/3m) (basic cost of film = rs 450.00/sq.mt)	21.00	SMT		
2	<b>SOFT BOARD PANELLING</b>				
	Providing and fixing 12mm thick soft board panelling with fabric on a 12 mm thick marine plywood backing. The backing shall be such that all its edges are finished with an old c.p. teak wood lipping patti with melamine polish finish and are recessed by 6mm on all 4 sides from the soft board. The fabric shall be neatly gladded on the soft board without any wrinkles or any kind of undulation. (basic rate of fabric – rs.225/- per meter).	40.00	SMT		

<b>BILL OF QUANTITIES – CIVIL AND INTERIOR FURNISHING WORKS</b>					
<b>Sr.</b>	<b>Particulars</b>	<b>Qty.</b>	<b>Unit</b>	<b>Rate (Rs.)</b>	<b>Amount (Rs.)</b>
3	<b>SIGNANGES</b>				
	Bank logo as per design.& as approved by architect. (combination of acrylic Bakelite & s.s finish)	4500.00	SQ.INCH		
4	<b>MIRROR FRAMES IN WASH BASIN AREAS</b>				
	Providing and fixing in position 6mm thick clear mirror with waterproof masking film at back side and computer polished edge fixed on 9mm thick marine ply wood back oil painted and fixing with 'I' section s.s. Frame work and complete all as per drawing detail /views and as directed by architect / bank engineer (mirror make : saint gobain / modi)	17.00	SMT		
5	Pelmet approx. 6" x 6" inside clear for roller blinds inside false ceiling with paint / laminate finished internally as directed.	15.00	RMT		
6	Providing and fixing in place roller blinds of approved make, quality, washable fabric and colour shade and pattern such as vista leveller/ Mac or approved equivalent. Rate shall include necessary scotch guards treatment on both sides complete. Basic cost of roller blind is rs.120/- per sqft.	290.00	SMT		
7	<b>ALUMINIUM WINDOWS</b>				
7.1	Providing and fixing sliding / open able aluminium section p/f sliding /open able windows with high-quality extruded aluminium alloy profiles T 6, 6061 with robust construction of • sections/profiles: includes outer frames (top, bottom, side), interlocking/ meeting stiles, and sliding sash members • gauge/thickness:1.8 MM • track configurations 3-track systems.(two glazes and aluminium one mosquito (SS net shutters) • glass : 5-6 mm tinted with tempered single glazing. • finish: approved colour anodized grade class 1 AA 20 micron,epdm gasket and silicon sealant etc.Locking:Multipoint locking • heavy duty (92 x 36.5mm. In 1.60 mm thick for bottom frame and 92 x 25mm. In 1.60 mm thick for top & side frames ) of approved make with 5- 6 mm thk.modiguard / saint gobain / asahi make clear float glass and imported beading shall be used. Complete ( prototype of sample to be provided for approval).leakage test to be conducted				
i	sliding window with mosquito track and SS mesh	320.00	sqm		
ii	Cascade window	100.00	sqm		
7.2	Providing and fixing fixed aluminium ventilators (z-sections for the frame and t-sections for mullions.)• p/f fixed glazed ventilator windows using high-quality extruded aluminium alloy profiles • heavy duty frame section (16 gauge): 32 - 40mm×18mm (approx. 0.456 kg/m). • glass compatibility: 5 -6 mm single glazing. • finish: approved colour anodized grade AA20 • approved make with 5- 6 mm thk.modiguard / saint gobain / asahi make clear float glass and imported beading (10.25mm to 12.7mm ) shall be used. Fixed directly into wall/ granite frame openings with appropriate screws and sealant. • complete ( prototype of sample to be provided for approval).	93.00	Sqm		
	NOTE:RATE SHALL BE INCLUSIVE OF NECESSARY APPROVED MAKE FITTINGS, integrated LOCKS, HANDLES, BEST QUALITY ROLLERS, NECESSARY HARDWARE ITEMS ETC. (JINDAL -SERIES "D"/ INDAL / HINDALCO MAKE ) AS PER SPECIFICATIONS & INSTRUCTIONS OF ARCHITECT.				
7.3	MS Grille for windows and balcony etc :Providing and fixing MS Grills made out of outer frame of 25mmx6mm . MS angle outer frame with MS Hold fastener and grill made out of 12mmX12 mm wrought iron square section at 100 mm centre to centre with horizontal frame work at 200mm centre to centre including wrought iron decorative bars. Fixing shall be suitably firmly fixed in the wall /stone etc and complete	11000.00	Kg		
7.4	<b>M.S. ROLLING SHUTTER</b>	9.00	SMT		
	Providing and fixing m. S. Rolling shutter of 18 gauge with side guides, bottom rail brackets, suspension shaft , all standard fittings, fixtures including mechanical gear, etc. Complete with painting of two coats of yellow oxide and three coats of enamel paint of approved shade etc. Complete.( for payment only masonry opening size will be considered ) location : rear exit of stc building				
8	<b>BUY BACK OFFER</b> (Note :all is where is ,as it is what it is basis" only				
1	Removing of existing flush door shutter approximately having size of 7'X3' installed in the rooms including ironmongeries etc without affecting existing frame and offering to the bank under buy back	46.00	Nos		
2	Removing of existing mosquito door approximately having size of 7'X3' installed in the hostel; rooms including ironmongeries etc without affecting existing frame and offering to the bank under buy back	46.00	Nos		

**BILL OF QUANTITIES – CIVIL AND INTERIOR FURNISHING WORKS**

<b>Sr.</b>	<b>Particulars</b>	<b>Qty.</b>	<b>Unit</b>	<b>Rate (Rs.)</b>	<b>Amount (Rs.)</b>
3	Removing of existing steel door/window including Grille having varies sizes installed in the windows opening including ironmongeries etc without affecting existing frame and offering to the bank under buy back	450.00	Sqm		
4	Removing of existing partition /panelling (to be redone) without affecting the existing structure including conduit/wiring etc and offering to the bank under buy back	100.00	Sqm		
6	Removing of existing false ceiling (to be redone) and removing from the site and offering to the same under buy back	200.00	Sqm		
7	Removing of existing unused /identified table for sale , having varies sizes 4and offering to the bank under buy back				
	6'X2'6"/2'0"	10.00	Nos		
	5'X2'6"/2'0"	10.00	Nos		
	4'x2'6'/2'0"	20.00	Nos		
	3'x2'0'/1'6"	10.00	Nos		
8	Removing of existing unused /identified sofa for sale , having varies sizes and offering to the bank under buy back				
i	single seater	10.00	Nos		
ii	Double seator	2.00	Nos		
iii	Triple Seator	3.00	Nos		
9	Removing of existing unused /identified chairs for sale , having varies ranges and offering to the bank under buy back				
	Computer/Class room/Dining room chair	70.00	Nos		
	Midback chair/Visitor chairs	40.00	Nos		
	High back Chairs	20.00	Nos		
10	Removing of existing unused /identified wooden storage for sale , having varies ranges and offering to the bank under buy back (Half height/Full height removal type only)	50.00	Sqm		
11	Removing of existing unused /identified steel almira storage for sale , having varies ranges and offering to the bank under buy back	40.00	Sqm		
	<b>TOTAL (EXCLUDING GST)</b>				
	<b>ADD 18% GST</b>				
	<b>GRAND TOTAL (INCLUDING GST)</b>				