

Ref No.:

Dated

#REF!

DETAILED ESTIMATE / SPECIFICATION FOR BILL OF QUANTITIES**OF AC WORK FOR INDIAN BANK**

#REF!

S. No.	DESCRIPTION	QUNTIY.	UNIT	RATE	AMOUNT
1	Suppy, Fixing, Testing & comissioning of following star rated AC units, with evaporator copper coil & imported refrigerant joints, with wireless remote controller (Make:- Bluestar / Voltas / Carrier)				
(i)	Cassette 2 TONE - INVERTER TECHNOLOGY	0.00	No.		
2	S.I.T.C. of 5 Star 1.5 Ton capacity High wall mounted Split A.C. comprising Indoor & Out-door units. Indoor unit comprising Multi Row DX cooling coil, expansion valve, drier, motor driven air-blower with metallic frame etc. Out-door unit will have rotory/scroll compressor, condenser coil, & fan, Cordless remote control unit etc. including refrigerant gas charging.	0	No.		
3	S.I.T.C. of 5 Star AC as per specifications given in item no 3 above But For 1.0T Split A.C.'s	0	NO		
2	SITC of interconnecting refrigerant pipe work with closed cell elastomeric nitrile rubber tublar in sulation between each set of indoor & outdoor units as per specification, all piping inside the room shall be peoperly supported with MS hanger & clamps including cabling from indoor to outdoor unit.				
(i)	Refrigerant Pipe for 2 TONE AC - INVETER (Cassette)	0.00	Rmt		
(ii)	Refrigerant Pipe for Split 2.0/1.5/1.0 TONE - INVERTER	53.00	Rmt		
3	Providing & fixing, testing and commissioning of wall mounted copper wound voltage stabilizer suitable for split all accessories. Input Voltage range : 140-280 V, Output : 230 V (Make:- LIVEGAURD/ Blue- Birds & Reputed Firm .)				
(i)	CAPACITY: 5 KVA	0.00	Nos		
(ii)	CAPACITY: 4 KVA	7.00	Nos		
4	Supplying and laying of Extra Electrical interconnecting control cable from indoor to outdoor of size as specified by the manufacturer suitable for 1.0 TR/ 1.5/2.0 TR Split type AC.	64.00	Rmt		
5	SITC of rigid CPVC piping complete with fittings supports as per specification tions & duly insulated with 6mm thick closed cell nitrile rubber insulation.				
(i)	Drain Pipe for 2.0 Tone AC (Cassette)	0.00	Rmt		
(ii)	Drain Pipe for Split 2.0/1.5 TR (Split)	35.00	Rmt		
6	M.S. stand with monkey cage - [In door & out door units	7.00	No		
7	Timer Machine Automatic in ATM	1.00	No.		
8	Installation Charges .	7.00	No		
Total					0.00
Note : GST will be extra.					