

INDIAN BANK  
Zonal Office, Chennai North Zone,  
First Floor, Krest Building,  
No.2, Jehangir Street, Chennai - 600 001

**PRICE BID**  
FOR THE PROPOSED INTERIOR, FURNISHING WORKS FOR ANNASALAI  
BRANCH, CHENNAI NORTH ZONE AT No: 2234, FIRST FLOOR, GEE GEE  
COMPLEX, ANNASALAI, CHENNAI 600 002

**SUMMARY**

**BRANCH WORKS**

Interior & Furnishing  
Electrical Works  
Lan Cabling Works

**Branch works total**

Base price	GST @ 18%		NETT

**In words Rupees**

Consultants:



No. 2L, Block - 2, Coromandel Park,  
543, Velachery Main Road, East Tambaram,  
Chennai 600 059. Mobile : 98412 81968





INDIAN BANK		
LIST OF MATERIALS TO BE USED IN THE WORK		
S.NO.	MATERIALS	BRAND NAME
1	Aluminium for frame work	Locally available - non anodised
2	Wooden frames for frame work foot rest etc.,	Malaysian Sal / Mahagony
3	Wood for frames and rebates, lipping, edging, etc.,	Beech wood/ Indian/ African Teak Wood (1st quality)
	All woods must be well seasoned, free from knots, other defects, due to handling and transportation. Wherever necessary, provide anti-termite treatment.	
4	Wood Preservative	Termisheild - (Asian Paints) Terminator - (Pidilite), STP - Pentaphene Pale
5	Plywood of all thickness	Green/ Century/ Archid (IS 303 - MR grade only)
6	Veneer	Green / Century/ Archid
7	Laminate	Sunmica
8	Adhesive for joints	Fevicol/ Vamicol - (SH Grade)
9	Adhesive for laminates	Fevicol/ Vamicol - (SR Grade)
10	Mortice/ Round Lock/ Night latch for doors	Godrej
11	Stainless steel hardwares such as Hinges, draw sliders, handles,	Ebco, Nikki, Dorset
12	Floor Spring	Dorma/ Ozone
13	Door Closer	Godrej only
14	Glass of all thickness	Saint Gobain/ Modi Guard
15	Wood primer/ Enamel Paint	Asian/ Nippon/ ICI
16	Wall primer/ Emulsion paint	Asian/ Nippon/ ICI
17	False ceiling (Gypsum board, angles, channels, clips etc.,)	Saint Gobain only
18	Vertical Blinds	Marvel Blinds/ Locally available
19	Hardwares and screws	Ebco, PTA etc.,



**INDIAN BANK - LIST OF MATERIALS TO BE USED IN THE WORK**

S.NO.	MATERIALS	BRAND NAME
	<b>ELECTRICAL WORKS</b>	
	Main switch/ Fuse units/ Switch Gears	L&T/ Bosma
	Main Distribution Board	Locally fabricated with L & T switch gears
	MCB distribution Boards/ MCB's	MDS Legrand/ L & T Hager/ Schneider
	Al. Ar. XLPE Cables	CCI/ Gloster/ Finolex/ Universal Cables
	Multi Strand Wire FRLSH grade	Finolex/ RR/ Polycab
	PVC Conduits	Locally available
	Pvc Insulation Tape Roll	Steel grip/ Deer/ Anchor
	Ac Starter, Plug Socket	Legrand/ L&T/ Siemens/North West
	Switches & Sockets	Anchor, Legrand
	Light Fittings	Elenserve/ Philips / Wipro
	Ceiling Fan & Wall Bracket Fans	Crompton/ Almonard/ Bajaj/ Polar
	Exhaust Fan	Almonard
	Calling Bell	GM
	Lugs	Dowells
	Terminals	Essen/Elmex
	<b>VOICE AND DATA WORKS</b>	
	Telephone Connectors	Krone Module
	Telephone Wires	Finolex, Polycab, Netco, Delton
	Telephone Jacks RJ -11	Modular switches as above
	Modular Racks	D-Link
	Cat - 6 UTP Cable	D-Link/ Molex
	16/24 Port Switches	D-Link/ Cisco/ Molex
	16/ 24 port Patch Panels	D-Link/ Cisco/ Molex
	Data Sockets - RJ - 45	Modular switches as above
	1Mtr/ 2 Mtr patch cords	Moulded D-Link



INDIAN BANK

**SCHEDULE OF QUANTITIES FOR THE PROPOSED INTERIOR, FURNISHING AND ELECTRICAL WORKS FOR ANNASALAI BRANCH AND ITS ONSITE E-LOUNGE, CHENNAI NORTH ZONE, AT No: 2234, FIRST FLOOR, GEE GEE COMPLEX, ANNASALAI, CHENNAI 600 002**

**INTERIOR FURNISHING WORKS**

Sl.	Description	Quantity	Rate	Unit	Amount
<b>A</b>	<b>PARTITIONS</b>				
1	<b>ENTRANCE 12MM GLASS DOOR</b> Providing entrance door using 12 mm thick clear float glass with teak wood top bottom and verticals of size 6" x 2 1/2" with glass etching as per standard design and pattern alround and logo at suitable height as directed including all accessories, 18" stainless steel handles on both sides and hardwares such as pivots at top, locks tower bolts etc., and polishing the rails to required shade to match the interior & exterior including all incidental materials etc., complete.,	126.00 Sft		Sft	
2	<b>WALL PANELLING</b> <b>Location: Entrance door and intermediate columns</b>  Providing wall panelling to the entrance door opening using 12/ 19 mm tk. MR grade plywood and lined with 1mm tk. laminate with necessary grooves of 1mm thick with teak wood lipping for the edges polished to match the interior. The rate shall include the cost of providing 100mm wide skirting with 1mm tk. laminate at base and a 100mm wide border at the top including all incidental materials and labour etc., complete.	400.00 Sft		Sft	
3	<b>TWO WAY AUTOMATIC FLOOR SPRING:</b> <b>Location: Entrance door</b> Providing two way automatic floor spring for the entrance door including top pivots, chasing the floor, fixing, grouting & finishing the same and making good including all incidental materials etc., complete.	6.00 No.s		Each	
4	<b>FULL HT. FULLY BLOCKED PARTITION</b> <b>Location: At Main door, Main rear partition, Power room, Record room etc.,</b> Providing full height double skin fully blocked partitions using aluminium frames of 2"x 1" size spaced at 2' 0" c/c maximum for the frame work, fixed with 6mm tk. MR grade plywood on both	1430.00 Sft		Sft	



Signature with

Sl.	Description	Quantity	Rate	Unit	Amount
	<p>sides and lined with 1mm tk. laminate with necessary grooves of 1mm thick. The rate shall include the cost of providing 100mm wide skirting with 1mm tk. laminate at base and a 100mm wide border at the top including making necessary slots for cable conduits to pass through and all incidental materials etc., complete.</p> <p>Suitable supports should be provided and the partition to be secured to the firm RCC ceiling if the partition lies within the false ceiling area but measurements will be taken upto false ceiling level if the partition lies within the false ceiling area.</p>				
5	<p><b>FULL HT. PARTLY GLAZED PARTITION</b>  <b>Location: Manager cabin front and sides.</b>            Providing full height double skin partly glazed partitions as per the partition specifications as above using all incidental materials, labour etc., and Manager front partition 12mm glass shall start from 0' 6" ht. and end at 7'0" ht. and for side partition 12mm glass shall start from 3' 0" and end at 7' 0" ht. from floor level. Suitable supports should be provided and the partition to be secured to the firm RCC ceiling but measurements will be taken upto false ceiling level.</p>	180.00 Sft		Sft	
6	<p><b>FULL HT. PARTLY GRILLED PARTITION:</b>  <b>Location : Strong room</b>            Providing full height, semi grilled plywood partition for strong room as per the partition specifications as above using all incidental materials and labour etc., and the partition shall start from floor level and end at grill ceiling or RCC ceiling as per the site condition and shall include the cost of providing ornamental aluminium grills to suitable sizes above 7'0" ht. and upto the MS. grill ceiling or RCC ceiling, complete.</p>	0.00 Sft		Sft	
7	<p><b>LOW HT PARTLY GLAZED PARTITION:</b>  <b>a Location : Counters/ Tables/ atm machines</b>            Providing low height double skin partitions for counters and tables in the banking hall as per the partition specifications as above but shall start at floor level and end at 4' 0" level using all materials and labour etc., Complete. The 12mm glass shall start from 3'0" and shall end at 4' 6" height.</p>	175.00 Sft		Sft	



Signature with

Sl.	Description	Quantity	Rate	Unit	Amount
8	<p><b>12MM TK GLAZING FOR COUNTER:</b>  <b>Location : Running counter, cash counter</b>            Providing front glazing for running counters from 2'6" ht. to 4' 0" ht. and cash counter from 3' 6" to 7' 0" ht. at customer side, using 12mm thick plain glass including edge polishing &amp; suitable etching as per standard design.</p>	120.00 Sft		Sft	
9	<p><b>FLUSH DOOR:</b>  <b>Location: All partitions</b>            Providing flush door shutter for manager and other partitions using 1 1/4" thick (30mm) solid core flush door with 1mm laminate with necessary grooves &amp; 12 mm etched glass as per design, fixed with teak wood ornamental moulding for the sides including necessary hardwares such as 5" stainless steel hinges, handles, door stopper etc.,            All the exposed edges of shutter shall be fixed with teak wood lipping and polished to match the interior/ colour scheme. 2 1/2" x 1" teak wooden frame work shall be screwed to the door opening in partition, as provided in window opening shall be provided as door frame rebate. The rate shall include the cost and fixing charges of round stainless steel mortise lock.</p>	126.00 Sft		Sft	
10	<p><b>DOOR CLOSER:</b>  <b>Location: As per detailed estimate</b>            Providing and fixing door closer for doors at manager, rear, power and record room partitions etc.,</p>	6.00 No.s		Each	
<b>B FALSE CEILING</b>					
1	<p><b>GYPSUM BOARD FALSE CEILING</b>  <b>Location: Banking hall</b>            Providing gyp board plain false ceiling using 12.5 mm thick gyp board "in the required/ dismantled places, after completion of all partitions newly proposed" suspended from ceiling and supported on sides using perimeter channels all round. The intermediate spaced at 4'0" c/c to be suspended at reqd. height. soffit cleat and ceiling angle at 4'0" c/c on either direction and ceiling channel at 2'0" c/c is then connected to intermediate channel by connecting clips to form the frame work.</p>	800.00 Sft		Sft	



Signature with

SI.	Description	Quantity	Rate	Unit	Amount
	Gyp board, then to be screwed to the ceiling channel and joints pasted with nylon gauze type tape and finished. All as per OEM's specification. The rate shall include making/providing openings for light fittings, A/c diffusers/ continuous grills etc., All such openings made shall be suitably reinforced and shall withstand the loads/vibrations which are likely to act, and finished with two or more coats of acrylic emulsion paint (white of ASIAN PAINTS) over two coats of putty.				
2	<b>GRID FALSE CEILING:</b> <b>Location: Manager cabin</b> Providing & fixing in position grid type false ceiling using Armstrong 600 mm x 600 mm x 15/ 16 mm Dune Supreme RH 99 Prima tile with regular edge or as available at site "for the dismantled/ damaged area" with frame work as specified by armstrong Co. with suspenders wherever required. Complete in all respects. (Note Only the plan area will be measured for payment. No extra payment will be made for cutouts, grooves, etc., )	120.00 Sft		Sft	
3	<b>ANODISED ALU. GRILL CEILING:</b> <b>Location: Cash Cabin</b> Providing and fixing in position readymade anodized aluminium grill of approved design and quality fixed with continuous teak wood beadings of approved shape (finished size shall be 35 x 25 mm) all round polished	40.00 Sft		Sft	
C	<b>COUNTERS &amp; TABLES</b>				
1	<b>RUNNING COUNTERS</b> <b>Location: Clerical counters with granite top</b> Providing and assembling banking counter as shown in drawing of size not less than 4' 6" x 2' 6" x 2' 6" with regular drawer - 1 No. and 1 shelf  on one side (right side), a keyboard drawer at centre and a platform for CPU onto other (left) side for each counter as shown in drawing using 19mm thick MR grade plywood pasted with  1.0mm thick laminate for all the exposed surfaces, including providing skirting 4" wide with 1.0mm thick laminate on both sides to match with the adjoining partition and 4" wide border at top with 1.0mm thick laminate as per design.	40.00 Rft		Rft	



Signature with

Sl.	Description	Quantity	Rate	Unit	Amount
	<p>All the plywood edges shall have teak wood lipping and all inner surfaces shall be pasted with 0.8 mm white/ light grey laminate of approved make.</p> <p>The rate shall include providing 20mm granite (Laxmi Red) for the work top. The rate shall include providing, fixing &amp; painting a foot rest using first class seasoned country frame of size 3" x1 1/2" and plywood foot rest shall not be provided. Necessary hardware fittings like draw sliders, hinges, multipurpose locks with set keys, handles, wire manager, shall be provided.</p>				
2	<p><b>CASH COUNTER:</b> Location: Cash counter with granite top</p> <p>Providing cash counter as per the above specification but including three drawers, one denomination drawer at top, two drawers below and an additional customer top at 3' 6" height with a low ht. transaction opening with the above specifications. Both the working and customer top shall be provided with granite (laxmi red) as per standards.</p>	5.50 Rft		Rft	
3	<p><b>FURNITURES:</b> <b>TABLES:</b> Manufacturing and placing in position of tables for managers &amp; staff using 19mm tk. MR grade plywood to size as shown in drawing.</p> <p>One keyboard drawer &amp; three storage drawers for manager tables, and one keyboard drawer at centre, one drawer at right or left side below conter top with storage cupboard with one shelf below for officer/staff tables, space to accomodate CPU etc., shall be provided..</p> <p>All the plywood edges shall have teak wood lipping &amp; the inner surfaces shall be painted or lined with laminate of 0.8 mm tk. The exposed surfaces and top shall be pasted with 1mm laminate.</p> <p>Necessary hardware fittings like draw sliders, lock, handles, wire manager etc., shall be provided. A sheet of 10 mm tk. plain float glass shall be provided over the manager tables only</p>				
a	Branch Manager 6' 0" x 3' 0"	1.00 No.s		Each	
b	Officer's Table 5' 0" x 2' 6"	4.00 No.s		Each	
c	Appraiser/ Audit table 4' 0" x 2' 6"	2.00 No.s		Each	



Signature with

Sl.	Description	Quantity	Rate	Unit	Amount
4	<p><b>STORAGE UNITS:</b></p> <p>Full Ht. Storage units - 8' 0"/ 7' 0" high  Low height storage - 2' 6"/ 3' 0" high</p> <p>Manufacturing and placing in position of side low height storage units 2' 6" high for officer tables using 19mm. tk. MR grade plywood as shown in drawing. Full ht. storages shall be 7'0"/ 8'0" as per site requirements</p> <p>All the plywood edges shall have teak wood lipping &amp; the inner surfaces shall be painted. The exposed surfaces shall be pasted with 1mm laminate with necessary grooves as per the drawing. Necessary hardware fittings like draw sliders, lock, handles etc., shall be provided. The existing storage units are to be kept in position without any disturbances.</p>	0.00 Sft 25.00 Sft		Sft Sft	
D	<b>FURNISHING ITEMS</b>				
1	<p><b>ORNAMENTAL PILLARS:</b></p> <p>Tall pillars - 7' 6" high  Short pillars - 5' 0" high</p> <p>Manufacturing and placing in position of side pillars to support the 12 mm glass front 5' 0" high for counters and 7' 6" high for cash counter using 19mm. tk. MR grade plywood as shown in drawing.</p>	2.00 No.s 6.00 No.s		Sft Sft	
2	<p><b>ROLLER BLINDS</b></p> <p><b>Location: Banking hall</b></p> <p>Dismantling the existing roller blinds, number and side marking, packing it safe and moving to CAPC general purpose room and re-fixing it in the same position after completion of work in its original position etc., complete.</p>	1.00 Job		Sft	
3	<p><b>NOTICE BOARD:</b></p> <p><b>Location: Banking hall</b></p> <p>Providing pinup board using soft board over 6 mm thick MR grade plywood with teak wood beadings at the edges, covered with fabric of basic price Rs.250/- per meter.(Maroon colour) The size shall be 2' 6" wide and 4' 0" high. Rear side shall be painted and beadings shall be polished. The rate shall include all incidental materials and labour etc., Complete.</p>	12.00 Sft		Sft	



Signature with

Sl.	Description	Quantity	Rate	Unit	Amount
4	<p><b>CHEQUE DROP BOX/ COMPLAINT BOX</b>  <b>Location: Banking hall</b>  Providing cheque drop box/ Complaint/ Suggestion box 1' 6" length, 0' 9" wide and 1' 6" height with 19mm tk. MR grade plywood and lined with 1mm tk. Laminate for top &amp; exposed sides. Exposed edges of plywood shall be fixed with teak wood beading suitably polished and the back side shall be covered with 6mm tk. BWP Grade plywood. The inner sides shall be painted with two coats of enamel paint over a coat of primer &amp; two coats of putty.</p>	2.00 No.s		Each	
5	<p><b>CHALLAN HOLDER/ WRITING LEDGE:</b>  <b>Location: Banking hall</b>  Providing writing ledge/ challan holder in the form of pigeon hole box 2' 6" length, 1' 6" wide and 6" height using 19mm tk. MR grade Plywood and lined with 1mm tk. Laminate for top &amp; exposed sides. Exposed edges of plywood shall be fixed with teak wood beading suitably polished and the back side shall be covered with 6mm tk. MR Grade plywood. The inner sides shall be painted with two coats of enamel paint over a coat of primer &amp; two coats of putty.</p>	1.00 No.		Each	
6	<p><b>WICKET GATE:</b>  <b>Location: Banking Hall</b>  Providing and fixing of 19mm tk. MR grade plywood door 3'0" high, pasted with 1mm tk. laminate on both sides with skirting and fixed to the low/ full ht. partitions etc., The rate shall include all hardwares such as screws, hinges, tower bolts, door stoppers etc., Complete. 3'0"x 3'0" minimum size.</p>	1.00 No.		Each	



Signature with

Sl.	Description	Quantity	Rate	Unit	Amount
E	<b>MISCELLANEOUS WORKS:</b>	1.00 Job		Job	
1	Dismantling the existing partitions of all types wherever necessary for the installation of the new branch including gypsum board false ceiling with minimal damages to the false ceiling, after disconnecting all the electrical fittings and making dummy the unwanted circuits/ connections etc., Existing cassette air-conditioners, electrical fittings and grid ceilings shall not be disturbed. All the debris shall be removed from the site to the contractors own site away from the site. The rate				
2	<b>COLOUR COATED GALVALUME SHEET:</b> Providing colour coated galvalume roofing sheet as a false ceiling in between the existing gypboard false ceiling and the regular RCC ceiling to avoid splashing/ leaking from the inaccessible upper floor construction joint as a measure to discharge the leakage water to gutter.	60.00 Sft		Sft	
3	Providing galvalume sheet gutter 12" wide x 6" deep upto 5mtrs in length, above the false ceiling for collecting leakage water including all fixing materials, clamps, consumables, scaffolding etc., complete.	1.00 Job		Job	
4	Providing 75mm PVC pipes as downfall pipes with specials as necessary fro the gal valume gutter to the ground level outside the building if space permits, including all scaffolding and consumables etc., complete.	1.00 Job		Job	
	Sub total				
	Add GST @ 18 %				
	Add to round off				
				Rs.	

In words Rupees

Contractor



Signature witi

INDIAN BANK

**SCHEDULE OF QUANTITIES FOR THE PROPOSED INTERIOR, FURNISHING AND ELECTRICAL WORKS FOR ANNASALAI BRANCH AND ITS ONSITE E-LOUNGE, CHENNAI NORTH ZONE, AT No: 2234, FIRST FLOOR, GEE GEE COMPLEX, ANNASALAI, CHENNAI 600 002**

**ELECTRICAL WORKS**

S. No.	Description	Quantity	Rate	Unit	Amount
<b>A</b>	<b>MAINS &amp; DISTRIBUTION BOARDS</b>				
1	All the main panel board, distribution board, and its connection including air-conditioners are to used as " as is where is " condition. Any changes required shall be brought to the notice of the employer/ Architect on commencement of the subject work.				
<b>B</b>	<b>POWER CABLES &amp; CONDUIT WIRING</b>				
a	All the existing cables provided and its connections to distribution boards, air-conditioners etc., are to be used as " as is where is " condition. Any changes required shall be brought to the notice of the employer/ Architect on commencement of the subject work.				
<b>C</b>	<b>END TERMINATIONS</b>				
1	All the existing cables end terminations provided and its connections to distribution boards, air-conditioners etc., are to be used as " as is where is " condition. Any changes required shall be brought to the notice of the employer/ Architect on commencement of the subject work.				
<b>D</b>	<b>AIR CONDITIONING WIRING &amp; ACCESSORIES</b>				
1	All the existing air-conditioning DB's wiring are not to bedisturbed and to be used as "as is where is" condition.				
<b>E</b>	<b>UPS WIRING &amp; ACCESSORIES</b>				
a	All the existing items such as UPS 60 Kva, input and output controls, UPS distribution boards shall be used as such. Except new circuits all items are to be re-used. Existing Circuit wiring shall be checked for its utility value and only the required changes/ additional wiring are allowed.				



Signature wit

S. No.	Description	Quantity	Rate	Unit	Amount
1	Wiring in position multi strand copper wire FRLSH grade 3 runs of 2.5.sq.mm cable for circuits from UPS DB to required places (counters, tables etc.) in P.V.C. conduit pipes including chasing in walls / floor wherever necessary. One loop may be provided and not more than two computers shall be connected to a circuit.	380.00 Mtr		Mtr	
2	Supply,fixing, testing & commissioning of 3No. 6A. 2/3 multi pin socket outlet in UPS power circuit controlled with two switches in a eight module anodised GI box, with modular top plate for all the above including dummies and incidental materials etc., for counters/ tables/ work stations.	20.00 Set		Set	
<b>F</b>	<b>RAW POWER</b>				
1	Wiring in position multi strand copper wire FRLSH grade 3 runs of 2.5.sq.mm cable for circuits from power D.B. to required places (counters and tables) in P.V.C. conduit pipes including chasing in walls / floor wherever necessary	300.00 Mtr		Mtr	
2	Supply,fixing, testing & commissioning of 3 No. 6A. 2/3 multi pin socket outlet in raw power circuit controlled with two switches in a eight module anodised GI box with modular top plate for all the above including dummies and incidental materials etc., for counters/ tables/ work stations. Only one loop shall be done for one more counter/ computer to the nearest counter/ tables/ work stations.				
		18.00 No		Each	
3	Supplying, fixing, testing and commissioning 16A multipin socket outlet with control switch in raw power circuit in steel sheet enclosure and modular top plate, etc., for work stations, printers & wall fans etc.,	4.00 No.s		No.s	



Signature wit

S. No.	Description	Quantity	Rate	Unit	Amount
<b>G</b>	<b>LIGHTING WIRING &amp; ACCESSORIES</b>				
1	Dismantling/ making dummies the unwanted wire connections provided for the earlier layout of electrical fittings to bare minimum required and providing additional wiring in position 3 runs of 2.5.sq.mm cable for circuits from LBD D.B. to required places (switch boards and others) in P.V.C. conduit pipes including chasing in walls / floor wherever necessary.	320.00 Mtr		Mtr	
2	Dismantling the existing switches, sockets, etc., connections to the electrical fittings, making corrections to the connections as per new layout the point wiring and supply, fixing, testing & commissioning of the following switch controls in steel sheet enclosure including 3 runs of 1.0 sqmm, steel sheet enclosure & modular top plate and all incidental materials etc., complete.				
a	Primary point	60.00 No.s		Each	
b	Secondary point	16.00 No.s		Each	
	1 fan controlled by step type regulator with switch				
c		2.00 No.s		Each	
d	Wall fan point including wires and switch boards	12.00 No.s		Each	
e	Exhaust fan point	2.00 No.s		Each	
f	1 No. 6A socket controlled by single switch in lighting switch board	10.00 No.s		Each	
g	1 No. 16A socket controlled by single switch in separate board for sign board timer control	6.00 No.s		Each	
h	1No. Buzzer with switch incl. wiring connections	1.00 No.s		Each	
<b>H</b>	<b>TELEPHONE WIRING &amp; ACCESSORIES</b>				
1	Wiring in position 1 run of e-cat 6, 4 pair 0.5 sqmm data cable as incomer for telephone cable in separate P.V.C. conduit pipes including chasing in walls / floor from service provider junction to krone box at manager cabin.	40.00 Mtr		Mtr	
2	Supplying fixing, testing and commissioning of 2 x 10 pair krone connector in powder coated steel sheet enclosure with all incidental materials etc., complete.	1.00 No.s		Each	
3	Wiring in position 1 run of 2 pair 0.5 sq.mm telephone cable in separate P.V.C. conduit pipes including chasing in walls / floor to necessary work stations.	280.00 Mtr		Mtr	



Signature wit

S. No.	Description	Quantity	Rate	Unit	Amount
4	Supply, fixing, testing and commissioning of RJ-11 telephone sockets in separate steel sheet enclosure including all incidental materials etc., complete.	17.00 No.s		Each	
<b>I</b>	<b>LIGHTING &amp; FIXTURES</b>				
1	All the existing light fittings are not to be disturbed and should be re-used as such in its own location and as is where is condition.				
2	Additional quantities of supply & fixing charges if required for the following light fittings with required hardwares such as suspension wires from ceiling, false ceiling, anchor fasteners, chains, bolts, nuts etc., complete.				
a	Supply & Installation of 2' 0" x 2' 0" Surface/ Recess mounted 33W LED lights with complete PMMA diffuser including necessary copper ballasts and fixing mounting frame/brackets. Brand: Philips, Model : as avilable at the site.	6.00 No.s		Each	
b	Supply & Installation of 15W high efficiency IRIS LED downlight luminiare with flushed diffuser including necessary fixing brackets. Make: Philips, Model : as available at site.	12.00 No.s		Each	
c	SFTC of Surface Mounted 4'0" - 1 x 20W LED Fittings with necessary accessories, etc., Make : Philips, Model : as available at site.	6.00 No.s		Each	
d	SFTC of Surface Mounted 2'0" - 1 x 10W LED Fittings with necessary accessories, etc., Model : Wipro- B531065	2.00 No.s		Each	
2	SFTC of 1200mm Sweep 5 Star rated - Group A Ceiling fan to be fixed on existing / erected clamps with necessary down rods and with all fixing accessories etc. Make : Crompton Greaves High speed plus - White	2.00 No.s		Each	
3	SFTC of 600mm Sweep 5 Star rated - Group A Ceiling fan to be fixed on existing / erected clamps with necessary down rods and with all fixing accessories etc. Make : Crompton Greaves High speed Ariya Briz - White	2.00 No.s		Each	



Signature wit

S. No.	Description	Quantity	Rate	Unit	Amount
4	Supply & Fixing of 400mm Sweep Wall mounted fan with accessories to be fixed on standard wall bracket connected with sheathed 3 core flex copper conductor. Group A cat. Make : Crompton Greaves High-flo	12.00 No.s		Each	
<b>K EARTHING</b>					
1	Existing earthing and earthing connections are to be re-used without any disturbances.				
2	Additional supply and laying charges of 8 SWG bare copper wire from the main D.B. to the earth pit or wherever required, including all accessories complete.	10.00 Mtr		Mtr	
3	Additional supply and laying of 6 Sqmm multi stranded copper wire for UPS earth in suitable PVC conduit wherever required, with all incidental materials etc., complete.	10.00 Mtr		Mtr	
	Sub Total Add GST @ 18%				
<b>TOTAL</b>				<b>Rs.</b>	

In words Rupees

Contractor



**INDIAN BANK**

**SCHEDULE OF QUANTITIES FOR THE PROPOSED INTERIOR, FURNISHING AND ELECTRICAL WORKS FOR ANNASALAI BRANCH AND ITS ONSITE E-LOUNGE, CHENNAI NORTH ZONE, AT No: 2234, FIRST FLOOR, GEE GEE COMPLEX, ANNASALAI, CHENNAI 600 002**

**LAN CABLING WORKS**

S. No.	Description	Quantity	Rate	Unit	Amount
<b>I</b>	<b>LAN/ DATA WIRING &amp; ACCESSORIES</b>				
1	Wiring in position 1 run of e-cat 6, 4 pair 0.5 sqmm data cable for computers in separate PVC conduit pipes including chasing in walls / floors from hub to necessary stations. (includes Branch & MCB office)	600.00 Mtr		Mtr	
2	Supplying, fixing testing commissioning of RJ-45 data sockets in separate enclosure including all incidental materials etc., complete.	21.00 No.s		Each	
3	Supply & fixing charges for 9U Hub Rack with Power Cord/ 6 sockets, panel and accessories.	1.00 No.s		Each	
4	Supply & fixing charges for jack panel of 24 Port.	1.00 No.s		Each	
5	Supply & fixing charges for 24 port switch 10/100 Mbps including connections.	1.00 No.s		Each	
6	Supply & fixing charges for cable organiser.	1.00 No.s		Each	
7	Supply & Laying of Cat 6 1Mtr Patch Cord	21.00 No.s		Each	
8	Supply & Laying of Cat 6 2Mtr Patch Cord	21.00 No.s		Each	
	Sub Total				
	Add GST @ 18 %				
<b>TOTAL</b>				<b>Rs.</b>	

In words Rupees

Contractor

