

**Gunjan and Associates**  
Architects, Engineers, Interiors  
& Landscape Designers  
141, Sainik Nagar, Raibareli Road, Lucknow-226002  
Phone: 0522-2441118, 9839018489, 9838818489  
E-mail: studio@gunjanandassociates.com  
URL: www.gunjanandassociates.com

**BILL OF QUANTITY FOR AIR-CONDITIONING WORKS**

**FOR INDIAN BANK, AT SASPAN, BRANCH & ATM**

Note;

1. Each vendor to specify the Make of A.C. they propose to supply.
2. Common drain pipes of Cassette / Split A.C.'s be terminated in any toilet Nahni traps OR else be terminated from external wall up to ground. AC's with COPPER Condenser & Evaporator coils only to be supplied.
3. Pl. enclose Technical Brocher of quoted A.C.'s.
4. As built layout drawing of Refrigerant & Drain Piping has to be attached with Final Bill.

Daikin, Hitachi, . AC's with COPPER Condenser & Evaporator coils should only be supplied.

Only one of these Makes to be quoted.

Pl. enclose Tech. Brocher of the quoted Cassette/ Split A.C.

S.N.	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
1	High Wall Split Inverter AC 1.0 Ton 5 star rating	No	3.00		
	SITC Of wall mounted split Inverter type AC 1.0 Ton 5 star.(AC MAKE of -VOLTAS DAIKIN,HITACHI `ONLY APPROVAL AS PER ARCHITECT with 5 year warranty on compressor and ecofriendly green gas.				
	<b>BM-1NO. ATM - NO.</b>				
2	High Wall Split Inverter AC 1.5 Ton 5 star rating	No	2.00		
	SITC Of wall mounted split Inverter type AC 1.5 Ton 5 star.(AC MAKE of -VOLTAS DAIKIN,HITACHI `ONLY APPROVAL AS PER ARCHITECT with 5 year warranty on compressor and ecofriendly green gas.				
3	Rate for Extra Piping (Rate above 12 Feet pipe which will be free with unit)Ref.Piping(Only single distance will be measured between Indoor & Outdoor Units)				
a	Copper Piping Refrigerant along with insulator Piping for Hi Wall 1.5 ton ,1 ton and 2 ton Ac 1/2 and 1/4 Soft Copper Refrigerant piping with complete fitting, elbows bends supporting arrangements Nissan, Merchant, MET tube, Totaline tube, pressure tested tube .	Rm	60.00		

4	<b>S.I.T.C. of 2X1.5sqmm core Copper conductor flexible cable between Indoor &amp; Outdoor Unit through holes made as above</b>	Rm	65.00		
5	Drain Water Piping Constructed out of PVC Hard Pipes, fitting, accessories, bends, elbows, tees, hanger, support, anchors, ISI approved Finolex/Prince Make <b>(32mm)</b>	RMT	45.00		
6	<b>Frame Work</b> Supply, Fabrication and installation Of MS base Frame for outdoor unit complete with epoxy painting vibration isolation pads, supports, hangers, railing brackets etc. with cage and lockning arrangment. (Thickness of bar - 10mm and min 30kg load capacity)	No	5.00		
7	Providing & Installation of 4KVA voltage Stabilizers with range of 130 - 280V of standard make as per the approval of the Architect of (Inmag, Servel, Stambh)	No	5.00		
8	timer for 2no. Ac in ATM with MCB breakers and wiring included	No.	1.00		
<b>Total</b>					

For GUNJAN & ASSOCIATES  
  
 (Ar. GUNJAN KAPUR)  
 PROPRIETOR

**Ar. Gunjan Kapur**

**M/s Gunjan & Associates**