

**BILLS OF QUANTITIES FOR FURNISHING WORK OF INDIAN BANK FOR
SPECIALIZED MSME BRANCH AHMEDABAD**

Sr. No.	Description	Quantity	Rate	Unit	Amount
[A] FURNISHING WORK FOR BRANCH					
1	CASH COUNTER	5		RFT	
2	SINGLE WINDOW COUNTER			RFT	
3	LOW HEIGHT COUNTER FOR OFFICER			RFT	
4	Providing & fixing Full height/Low height partition with door shutter For Manager and other area Note :Rate shall be same for solid partition	128.00		SFT	
5	Providing and fixing low height partition For Cash /S.W Cabin and other partition	150		SFT	
6	Providing and fixing Isolated flush door shutter	35		SFT	
7	Providing and fixing Wicket Gate door in Cash cabin	12		SFT	
8	Providing and laying pannelling on walls & pillars at main entrance door and 18mm thick plywood box for entrance door and AC pipe covering	380		SFT	
9	Providing and fixing Glass partition on Cash counter/ SW Counter / Low Height counter front side top as follows.	33.00		SFT	
10	Suppling and providing BM Table as per the following description Size 6'-0" x 2'-9". Table top shall be made for 18mm thick commercial	1		NO	
10	'-DO- as above but S/P Officer Table Approx Size 4'-0" x 2'-6". With 1 Nos Drawer+ 1 Shutter unit for Officer	2		NO	
11	'-DO- as above but S/P Officer Table Approx Size 5'-0" x 2'-6". Without Drawer Unit in table	4		NO	
12	Supplying and providing side cabinate for keeping computer and printer size 3'-0" or 3'-3" Length 1'-4" Width and 2'-6" height. Having openable shutters as directed.	4		NO	
13	Supplying and providing side storage cabinate as per following description. [Low Height and Full Height]	77		SFT	
14	Providing and fixing Electric cup board using 18mm thick commercial ply wood with 1.0 mm thick laminate on outer side polishing/painting	35		SFT	
15	Providing soft board for pin up	8		SFT	
16	CUSTOMER WRITING DESK 'Size 3'-0" x 1'-0" x 6" ht.	1		NO	

Sr. No.	Description	Quantity	Rate	Unit	Amount
17	Providing and fixing of letter box cum suggestion box of size 1' 3"x1'-0" x 3'-6" ht. Box	1		NO	
18	Providing and fixing "EG/Godrej" or equivalent make door closure.	4		NO	
*	GLASS WORK				
	12 MM THICK TOUGHEND GLASS DOOR & PARTITION				
19	[I] OPENABLE PORTION Without Floor Spring	42		SFT	
20	[II] FIXED GLASS PORTION	193.00		SFT	
24	Providing and Fixing Floor Spring of Avertie or equivalent make heavy duty & double swing.	0		NO	
21	ALUMINUM COMPOSITE PANEL FOR FRONT SIDE ELEVATION	255		SFT	
22	Providing and fixing Gypsum board 12.50 mm thick false ceiling in steps and design using Original Indian Gypsum board	200.00		SFT	
23	Providing and fixing of Armstrong Mineral Fibre Acoustical Suspended Ceiling System with 16 mm thick FINE FISSURED (MICRO LOOK) EDGE TILES WITH ARMSTRONG SELECT (Black Reveal) 15 mm EXPOSED GRID.	448.00		SFT	
TOTAL COST OF FURNISHING WORK				RS.	_____